

**SIDEWALK**

STATION BEGIN	STATION END	LENGTH WALK ON CL (FOOT)	WIDTH (FOOT)	STAMPED COLORED PCC SIDEWALK 5" (FOOT)	DETECTABLE WARNINGS (SQ FT)	AGGREGATE BASE COURSE TYPE B - 4" (SQ YD)	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT (SPECIAL) (FOOT)	HOT-MIX ASPHALT REMOVAL (PAID FOR AS SIDEWALK REMOVAL) (SQ FT)	SIDEWALK REMOVAL (SQ FT)
ILLINOIS ROUTE 137 (SHERIDAN ROAD)									
46 + 69 LT	49 + 70 LT	210	5	1,233	10	137	—	760	—
50 + 11 LT	54 + 74 LT	463	5	1,728	40	192	—	1,050	625
—	—	—	—	—	—	—	—	—	—
46 + 69 RT	49 + 60 RT	291	5	1,389	40	121	—	700	585
50 + 30 RT	54 + 74 RT	444	5	2,052	20	228	—	—	2,210
SUBTOTAL ILLINOIS ROUTE 137 (SHERIDAN ROAD)				6,402	110	678	—	2,510	3,420
7TH STREET									
6 + 44 LT	6 + 77 LT	33	5	306	10	34	—	—	306
7 + 07 LT	9 + 77 LT	270	5	1,512	60	183	45	—	1,512
10 + 39 LT	12 + 94 LT	255	VAR	4,860	20	555	42	—	4,245
12 + 94 LT	15 + 74 LT	280	5	1,503	20	167	—	—	1,400
15 + 74 LT	18 + 69 LT	298	5	1,593	30	184	30	—	1,753
18 + 96 LT	22 + 56 LT	360	5	2,106	30	250	92	—	1,670
22 + 81 LT	27 + 81 LT	500	5	2,385	100	275	39	—	2,000
—	—	—	—	—	—	—	—	—	—
6 + 48 RT	6 + 72 RT	24	5	153	10	17	—	—	—
6 + 92 RT	9 + 63 RT	271	5	1,620	60	195	45	120	1,370
10 + 50 RT	12 + 75 RT	275	5	1,656	50	198	40	—	1,940
13 + 03 RT	15 + 59 RT	256	5	1,629	20	192	44	—	1,325
15 + 86 RT	18 + 89 RT	303	5	1,800	20	211	45	—	1,600
19 + 18 RT	22 + 70 RT	352	5	2,097	20	244	47	—	—
22 + 70 RT	27 + 81 RT	511	5	2,268	10	256	17	—	—
SUBTOTAL 7TH STREET				25,488	460	2,967	486	120	19,121
TOTAL				31,890	570	3,645	486	2,630	22,541
									+ 2,630
									= 25,171

**AGGREGATE BASE COURSE**

STATION BEGIN	STATION END	AGGREGATE BASE COURSE TYPE B - 4" (SQ YD)	AGGREGATE BASE COURSE TYPE B - 6" (SQ YD)
ILLINOIS ROUTE 137 (SHERIDAN ROAD)			
46 + 69 LT	50 + 00 LT	45	20
50 + 00 LT	54 + 74 LT	46	—
—	—	—	—
46 + 69 RT	49 + 60 RT	80	—
50 + 30 RT	54 + 74 RT	50	—
FROM ILLINOIS ROUTE 137 (SHERIDAN ROAD) HMA SCHEDULE		129	—
FROM ILLINOIS ROUTE 137 (SHERIDAN ROAD) SIDEWALK SCHEDULE		678	—
FROM ILLINOIS ROUTE 137 (SHERIDAN ROAD) DRIVEWAY SCHEDULE		177	120
SUB TOTAL FROM ILLINOIS ROUTE 137 (SHERIDAN ROAD)		1,205	140
7TH STREET			
10+39 RT	12+94 RT	488	46
FROM HMA SCHEDULE		345	—
FROM 7TH STREET SIDEWALK SCHEDULE		2,967	364
FROM 7TH STREET DRIVEWAY SCHEDULE		695	—
SUB TOTAL FROM 7TH STREET		4,495	405
TOTAL		5,700	545

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.  
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 LICENSE NO. 184-00121 - EXPIRES 4/30/2011  
 10/16/2009 4:00:08 PM \\s:\p\m\060807\Draws\Schedule.sht



DESIGNED - MWP	REVISED - IDOT REVIEW 2/19/09
DRAWN - CJC	REVISED - IDOT REVIEW 4/22/09
CHECKED - MDW	REVISED -
DATE - 8-1-08	FILE - 060807-schedule.sht

**VILLAGE OF WINTHROP HARBOR, ILLINOIS**  
**ILLINOIS ROUTE 137 (SHERIDAN ROAD) AND 7th STREET**  
**STREETScape IMPROVEMENTS**

**SCHEDULE OF QUANTITIES**

SCALE: NONE STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	06-00036-00-LS	LAKE	70	14
FED. ROAD DIST. NO. 1		CONTRACT NO. 63167		
JOB NO. C-91-197-10		ILLINOIS FED. AID PROJECT ARA-0001(810)		

\* F.A.P. 352 ILLINOIS ROUTE 137 (SHERIDAN ROAD)