

SUMMARY OF QUANTITIES

ITEM NO.	PAY ITEM	UNIT	TOTAL
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	250
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4
25200110	SODDING, SALT TOLERANT	SQ YD	250
25200200	SUPPLEMENTAL WATERING	UNIT	5
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,122
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	471
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	810
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,011
42400800	DETECTABLE WARNINGS	SQ FT	30
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	11,221
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	869
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	67
44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	12,031
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	6
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, AND OPEN LID	EACH	5
60266600	VALVE BOXES TO BE ADJUSTED	EACH	3
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,200
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,062
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	148
44004600	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	2,420
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	25
XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	25
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	15

* SPECIALTY ITEM



**VILLAGE OF HOMEWOOD
ENGINEERING DIVISION**

DESIGNED BY:	D.J.A.
DRAWN BY:	D.J.A.
CHECKED BY:	M.M.

REVISIONS			
NO.	DATE	BY	DESCRIPTION

VILLAGE OF HOMEWOOD 187th STREET L.A.P.P. PROJECT SUMMARY OF QUANTITIES	
DATE:	10-14-09
SCALE:	NOT TO SCALE

SHEET 2 OF 10
