

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1617	09-00077-00-RS	COOK	9	3
STA.	N/A	TO STA.	N/A	
FED. ROAD DIST. NO.	ILLINOIS			

SUMMARY OF QUANTITIES

CODED ITEM NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY 1000	NON PARTICIPATING 100% VILAGE OF HAZEL CREST
20200100	EARTH EXCAVATION	CU YD	50	50	
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	50	50	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,900	1,900	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	570	570	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	910	910	
40603310	HOT-MIX ASPHALT, SURFACE COURSE, MIX "C", N50	TON	1,185	1,185	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	60	60	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	750	750	
42400800	DETECTABLE WARNINGS	SQ FT	300	300	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	4,200	4,200	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	60	60	
44000600	SIDEWALK REMOVAL	SQ FT	750	750	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	900	900	
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	24	24	
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	50	50	
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	115	115	
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	805	805	
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	6	6	
60403600	GRATES, SPECIAL	EACH	17		17
60500050	REMOVING CATCH BASINS	EACH	1	1	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	925	925	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	75	75	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	20	20	
X0322052	ASPHALT REJUVENATING AGENT	GALLON	1,260	1,260	
X0324096	HOT IN-PLACE RECYCLING	SQ YD	12,510	12,510	
XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	275	275	

* DENOTES SPECIALTY ITEMS

SCHEDULE - PCC SIDEWALK REMOVAL AND REPLACEMENT

LOCATION		SIDEWALK REMOVAL AND REPLACEMENT SQ. FT.	DETECTABLE WARNINGS SQ. FT.
INTERSECTION	CORNER		
BURR-OAK LANE	SW	45	16
	SE	60	35
HICKORY LANE	SE	90	35
	SW	80	30
HAZEL LANE	NE	50	16
	NW	60	16
	SW	55	25
	SE	0	0
WOODWORTH PLACE	NE	0	0
	NW	0	0
	SW	40	15
	SE	30	15
OAK STREET	NE	50	16
	SE	50	16
MAPLE LANE	NE	55	20
	NW	25	16
	SW	30	16
	SE	30	10

SCHEDULE - DRIVEWAY REMOVAL AND REPLACEMENT

ADDRESS	DRIVEWAY AREAS, SQ. YDS	
	PCC	HMA
173rd STREET		
3321	20.00	
3409		25.50
ELM DRIVE		
17205		24.50
17204	13.50	
17202		30.00
17201		22.00
17119		19.00
17118		17.00
17117	23.00	
17116		16.00
17115		16.00
17112		25.00
17110		22.00
17109		17.00
17108		22.00
17107		15.00

P:\oad\MS\0\Plt\Drivers\Pen Tables\uct.tbl

P:\oad\MS\0\Plt\Drivers\ace-grajicob.tbl

CIVIL / STRUCTURAL ENGINEERS



GLOBETROTTERS INTERNATIONAL
300 SOUTH WACKER DRIVE, SUITE 200
CHICAGO, IL. 60606

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES

HAZEL CREST, IL

SCALE: VERT. NONE
HORIZ. NONE
DATE 10/15/09

DRAWN BY BS
CHECKED BY NC