

SUMMARY OF QUANTITIES					PAVEMENT	SIDEWALKS	TRAFFIC
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE		SIGNALS
					I000	SFTY-1B	Y031-1F
	20800150	TRENCH BACKFILL	CU YD	75	75		
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	800	800		
	21400100	GRADING AND SHAPING DITCHES	FOOT	460	460		
	25200650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	800	800		
	28000305	TEMPORARY DITCH CHECKS	EACH	40	40		
	28000510	INLET FILTERS	EACH	3	3		
	28100105	STONE RIPRAP, CLASS A3	SQ YD	3	3		
	35101400	AGGREGATE BASE COURSE, TYPE B	TON	105		105	
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	22	22		
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4	4		
	42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	3700		3700	
	42400800	DETECTABLE WARNINGS	SQ FT	80		80	
	44000100	PAVEMENT REMOVAL	SQ YD	115	115		
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	94	94		
	44000600	SIDEWALK REMOVAL	SQ FT	160		160	
	44002300	CURB REMOVAL (PARTIAL)	FOOT	75	75		
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	47	47		
	50105220	PIPE CULVERT REMOVAL	FOOT	20	20		
	54200215	PIPE CULVERTS, CLASS C, TYPE 1, 10"	FOOT	7	7		
	54213453	END SECTIONS 18"	EACH	3	3		
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	120	120		
	55100900	STORM SEWER REMOVAL 18"	FOOT	420	420		
	60207605	CATCH BASINS, TYPE C, TYPE B GRATE	EACH	1	1		
	60207000	CATCH BASINS, TYPE A, TYPE B GRATE	EACH	1	1		
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2		
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	40	40		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	69	69		
	67100100	MOBILIZATION	L SUM	1	1		
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	454	454		
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	92	92		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	248	248		
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	8			8
*	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	24			24
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	448			448
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	640			640
*	87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	2			2
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8			8
*	87900200	DRILL EXISTING HANDHOLE	EACH	2			2
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2			2
*	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1			1
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	3			3
*	89502200	MODIFY EXISTING CONTROLLER	EACH	1			1
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52		

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 07434-QUAN-01	USER NAME =	DESIGNED -- V.C.	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MANHATTAN ROAD SIDEWALK IMPROVEMENTS			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = N/A	CHECKED -- V.C.	REVISED --		SUMMARY OF QUANTITIES, GENERAL NOTES AND CROSS SECTIONS			0532	09-00009-00-SW	WILL	13	2
	PLOT DATE = 07-30-09	DRAWN -- LTL	REVISED --		SCALE: N/A	SHEET NO. 2 OF 13 SHEETS	STA.	TO STA.	CONTRACT NO. 63309			
		CHECKED -- V.C./J.R.	REVISED --		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003 (360)							