

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONSTRUCTION CODE 1000 TOTAL QUANTITY
x 20201006	GRADING AND SHAPING SHOULDERS	UNIT	19
x 20800250	TRENCH BACKFILL, SPECIAL	CU YD	12
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	467
40600300	AGGREGATE (PRIME COAT)	TON	10
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	263
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	73
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	657
x 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	526
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	4495
x 44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	75
x 44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	52
x 44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	778
x 44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	4495
48101200	AGGREGATE SHOULDERS, TYPE B	TON	136
x 50105225	PIPE CULVERT REMOVAL (SPECIAL)	FOOT	64
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	32
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	32
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
x XX006806	HOT-MIX ASPHALT DRIVEWAY REPLACEMENT	SQ YD	228
x XX007365	HOT-MIX ASPHALT DRIVEWAY SURFACE REMOVAL - DRIVEWAY BUTT JOINT	SQ YD	228

- INDICATES SPECIALTY ITEM
- x INDICATES NON-STANDARD ITEM COVERED BY SPECIAL PROVISION

▲ Revised

PATCHING SCHEDULE

STA	TO STA	O/S	WIDTH	TYPE II (SQ YD)	TYPE III (SQ YD)	TYPE IV (SQ YD)
6+62	6+92	RT	5		16.7	
6+92	7+08	LT	4	7.2		
7+93	8+06	LT	10	14.5		
9+00	10+00	FULL WIDTH	20			222.3
10+53	10+70	RT	10		18.9	
10+77	10+84	FULL WIDTH	20		15.6	
10+84	10+94	LT	10	11.2		
11+88	12+08	FULL WIDTH	22			48.9
12+08	12+18	RT	11	12.3		
13+34	13+47	FULL WIDTH	21.5			31.1
16+96	18+78	FULL WIDTH	20			404.5
19+74	19+79	FULL WIDTH	20	11.1		
19+92	19+97	FULL WIDTH	20	11.1		
20+00	20+36	RT	11			44.0
20+36	20+39	FULL WIDTH	22	7.4		
20+70	21+00	CENTERLINE	8			26.7
SUB TOTALS:				75.0	52.0	778.0
TOTAL:				905.0		SQ YD

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-00034-00-RS	COOK		8	3
STA.	TO STA.			

FED. ROAD DIST. NO. ILLINOIS FED AID PROJECT
C-91-740-09 ARA-9003(525)

FAU 1705 173RD STREET
CONTRACT NO. 63315

DRIVEWAY SCHEDULE

CL STA		DW WIDTH	DW SQ YD 3 FT DEEP
08+00	RT	194	64.7
08+79	LT	16	5.3
10+45	RT	64	21.3
11+46	LT	40	13.3
11+94	RT	48	16.0
12+30	LT	36	12.0
13+38	RT	38	12.7
14+82	RT	44	14.7
15+15	LT	20	6.7
16+09	LT	20	6.7
16+86	RT	34	11.3
17+78	RT	12	4.0
19+56	LT	20	6.7
20+50	RT	32	10.7
21+98	LT	66	22.0
TOTAL (SQ YD) =		228.0	

COPYRIGHT © 2005 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 4882CC
 10/27/2009
 \\\C:\p\d\3000000000\3000\Projects\Mokemo\CCH\090389-173rd\APRA\CADD\SURVEY\DRAWINGS\DRNS\090389-500.shp



DESIGNED - JGH	REVISED - PER IDOT 10-6-09
DRAWN - BCD	REVISED -
CHECKED - NJP	REVISED -
DATE - 8-06-09	FILE - 090389-500.shp

CITY OF COUNTRY CLUB HILLS, ILLINOIS
FAU 1705 173RD STREET
RESURFACING

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-00034-00-RS	COOK		8	3
FED. ROAD DIST. NO. ILLINOIS			FED. AID PROJECT	
			CONTRACT NO. 63315	