# SUMMARY OF QUANTITIES

| | CODE NO. | DESCRIPTION | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE | | |
|---|---|---|---|---|---|---|---|
| | | | | | ROADWAY 1000-1A | SIGNALS Y031-1F | SIDEWALK Y044 |
| ** | 28000305 | TEMPORARY DITCH CHECKS | FOOT | 10 | 10 | | |
| ** | 28000400 | PERIMETER EROSION BARRIER | FOOT | 95 | 95 | | |
| ** | 28000510 | INLET FILTER | EACH | 2 | 2 | | |
| x ** | 35101600 | AGGREGATE BASE COURSE, TYPE B 4" | SQ YD | 133 | 133 | | |
| x ** | 40603310 | HOT-MIX ASPHALT SURFACE COURCE, MIX "C", N50 | TON | 2 | 2 | | |
| x ** | 42400430 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL | SQ FT | 949 | 949 | | |
| x ** | 42400800 | DETECTABLE WARNINGS | SQ FT | 80 | 80 | | |
| x ** | 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 94 | 94 | | |
| x ** | 44004700 | SIDEWALK REMOVAL (SPECIAL) | SQ FT | 444 | 444 | | |
| | 67100100 | MOBILIZATION | L SUM | 1 | 1 | | |
| x | 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | | |
| x | 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | | |
| x | 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | |
| x | 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | | |
| | 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 16 | 16 | | |
| | 72000100 | SIGN PANEL, TYPE 1 | SQ FT | 64.5 | 36 | 28.5 | |
| x | 72400100 | REMOVE SIGN PANEL ASSEMBLY, TYPE A | EACH | 5 | 5 | | |
| | 72900100 | METAL POST, TYPE A | FOOT | 100 | 100 | | |
| •• | 78000400 | THERMOPLASTIC PAVEMENT MARKING, LINE 6" | FOOT | 608 | 608 | | |
| •• | 78000600 | THERMOPLASTIC PAVEMENT MARKING, LINE 12" | FOOT | 169 | 169 | | |
| •• | 78000650 | THERMOPLASTIC PAVEMENT MARKING, LINE 24" | FOOT | 140 | 140 | | |
| x | 81000600 | CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL | FOOT | 584 | | 584 | |
| | 81000700 | CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 28.5 | | 28.5 | |
| | 81000800 | CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL | FOOT | 8 | | 8 | |
| | 81001100 | CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL | FOOT | 10 | | 10 | |
| | 81018500 | CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 71 | | 71 | |
| | 81018600 | CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 87 | | 87 | |
| | 81018900 | CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL | FOOT | 336 | | 336 | |
| | 81019000 | CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL | FOOT | 28 | | 28 | |
| | 81400700 | HANDHOLE, PORTLAND CEMENT CONCRETE | EACH | 4 | | 4 | |
| | 81400710 | HEAVY DUTY HANDHOLE, PORTLAND CEMENT CONCRETE | EACH | 5 | | 5 | |
| | 81400720 | DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE | EACH | 2 | | 2 | |
| | 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 934 | | 934 | |
| | 85700200 | FULL - ACTUATED CONTROLLER AND TYPE IV CABINET | EACH | 1 | | 1 | |
| | 86200200 | UNITERRUPTABLE POWER SUPPLY, STANDARD | EACH | 1 | | 1 | |
| | 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C | FOOT | 1316 | | 1316 | |
| | 87301225 | ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C | FOOT | 1904 | | 1904 | |
| | 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C | FOOT | 921 | | 921 | |
| | 87301255 | ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C | FOOT | 1760 | | 1760 | |
| | 87301305 | ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR | FOOT | 1884 | | 1884 | |
| | 87301805 | ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6, 2C | FOOT | 95 | | 95 | |
| | 87502500 | TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT. | EACH | 3 | | 3 | |

•• DENOTES SPECIALTY ITEMS
x DENOTES ITEMS REFERENCED IN A SPECIAL PROVISION

Revised 12-14-09

COPYRIGHT © 2005, BY BAXTER & WOODMAN, INC.
LICENSE TO IDOT PROFESSIONAL ENGINEER
LICENSE NO.: 184-001121 EXPIRES: 4/30/2011
566bcd 0/6/2009 9:06:15 AM
...\bmf-f-jpr\09F223\3.sht
...\CADD-SURVEY\VLOTS\BB.tbl
\\Corp.baxwood.com\projects\Makena\Wich\071621-Lrwy at Wolf\CADD-SURVEY\DRAWINGS\DCNS\071621-soq.sht

BAXTER & WOODMAN Consulting Engineers

| | | | |
|---|---|---|---|
| DESIGNED - NJP | REVISED - PER COUNTY 8-20-09 | WILL COUNTY DEPARTMENT OF HIGHWAYS | SUMMARY OF QUANTITIES |
| DRAWN - BCD | REVISED - PER IDOT 09-16-09 | LARAWAY ROAD AT WOLF ROAD | |
| CHECKED - RWL | REVISED - | | SCALE: STA. TO STA. |
| DATE - 06-25-09 | FILE - 071621-soq.sht | | |

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 320 | 07-00138-26-TL | WILL | 19 | 4 |
| C-91-405-08 | | CONTRACT NO. 63329 | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |