

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 1000-1A	SIGNALS Y031-1F	SIDEWALK Y044
** 28000305	TEMPORARY DITCH CHECKS	FOOT	10	10		
** 28000400	PERIMETER EROSION BARRIER	FOOT	95	95		
** 28000510	INLET FILTER	EACH	2	2		
x ** 35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	133	133		
x ** 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2	2		
x ** 42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	949	949		
x ** 42400800	DETECTABLE WARNINGS	SQ FT	80	80		
x ** 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	94	94		
x ** 44004700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	444	444		
	67100100	MOBILIZATION	L SUM	1	1	
x	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
x	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
x	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
x	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16	
	72000100	SIGN PANEL, TYPE 1	SQ FT	64.5	36	28.5
x	72400100	REMOVE SIGN PANEL ASSEMBLY, TYPE A	EACH	5	5	
	72900100	METAL POST, TYPE A	FOOT	100	100	
**	78000400	THERMOPLASTIC PAVEMENT MARKING, LINE 6"	FOOT	608	608	
**	78000600	THERMOPLASTIC PAVEMENT MARKING, LINE 12"	FOOT	169	169	
**	78000650	THERMOPLASTIC PAVEMENT MARKING, LINE 24"	FOOT	140	140	
x	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	584		584
	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	28.5		28.5
	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	8		8
	81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	10		10
	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	71		71
	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	87		87
	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	336		336
	81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	28		28
	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4		4
	81400710	HEAVY DUTY HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5		5
	81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2		2
	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	934		934
	85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
	86200200	UNITERRUPTABLE POWER SUPPLY, STANDARD	EACH	1		1
	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	1316		1316
	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1904		1904
	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	921		921
	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	1760		1760
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1884		1884
	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6, 2C	FOOT	95		95
	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	3		3

** DENOTES SPECIALTY ITEMS
x DENOTES ITEMS REFERENCED IN A SPECIAL PROVISION

Revised 12-14-09

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 LICENSE NO. 184-00101 - EXPIRES 4/30/2011
 10/15/2009 9:06:05 AM
 \\Corporation\woodman\projects\Wills\071621-soq.dwg



DESIGNED - NJP	REVISED - PER COUNTY 8-20-09
DRAWN - BCD	REVISED - PER IDOT 09-16-09
CHECKED - RWL	REVISED -
DATE - 06-25-09	FILE - 071621-soq.sht

**WILL COUNTY DEPARTMENT OF HIGHWAYS
 LARAWAY ROAD AT WOLF ROAD**

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	07-00138-26-TL	WILL	19	4
C-91-405-08			CONTRACT NO. 63329	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 1000-1A	SIGNALS Y031-1F	SIDEWALK Y044
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1		1	
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1	
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1		1	
87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1		1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12		12	
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4	
87800400	CONCRETE FOUNDATION, TYPE E 30" DIAMETER	FOOT	15		15	
87800415	CONCRETE FOUNDATION, TYPE E 36" DIAMETER	FOOT	45		45	
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4		4	
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4	
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4		4	
88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	6		6	
88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	1		1	
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	8		8	
88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8	
88600100	DETECTOR LOOP, TYPE 1	FOOT	1052		1052	
88700200	LIGHT DETECTOR	EACH	2		2	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1	
x 88800100	PEDESTRIAN PUSH BUTTON	EACH	7		7	
X8050015	SERVICE INSTALLATION, POLE MOUNTED	EACH	1		1	
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1173		1173	
X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	330		330	

•• DENOTES SPECIALTY ITEMS
x DENOTES ITEMS REFERENCED IN A SPECIAL PROVISION

Revised 12-14-09

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 ALL RIGHTS RESERVED. PROJECT NO. 071621-14-014
 LICENSE NO. 014-00129 - EXPIRES 4/30/2011
 \\corpdbaxwood.com\p0\projects\mkene\071621-14-014\071621-14-014-014.sht



DESIGNED - NJP	REVISED - PER COUNTY 8-20-09
DRAWN - BCD	REVISED - PER IDOT 09-16-09
CHECKED - RWL	REVISED -
DATE - 06-25-09	FILE - 071621-soq.sht

**WILL COUNTY DEPARTMENT OF HIGHWAYS
 LARAWAY ROAD AT WOLF ROAD**

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	07-00138-26-TL	WILL	19	5
C-91-405-08			CONTRACT NO. 63329	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				