SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONSTRUCTION CODE 1000
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	798
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	20
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,449
40600300	AGGREGATE (PRIME COAT)	TON	49
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	156
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,155
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	32
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5,570
42400800	DETECTABLE WARNINGS	SQ FT	60
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	24,490
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	54
44000600	SIDEWALK REMOVAL	SQ FT	5,570
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	562
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,050
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	400
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	350
60266610	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	2
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	41
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,400
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	200
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	255
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15,206
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,464
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	851
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	210
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	263
78300100	PAVEMENT MARKING REMOVAL	SQ FT	300
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	263
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	295
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	208
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,127

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-001008 EXPIRES 4/30/2010
10/26/2009 3:06:27 PM
26.3inc

BAXTER & WOODMAN Consulting Engineers

DESIGNED - SLN	REVISED - IDOT REVIEW 10/05/09	CITY OF HIGHWOOD, ILLINOIS SHERIDAN ROAD ARRA (LAPP) RESURFACING	SUMMARY OF QUANTITIES
DRAWN - KAR	REVISED - IDOT REVIEW 10/26/09		SCALE: NONE STA. TO STA.
CHECKED - RWL	REVISED -		
DATE - 08-20-09	FILE - 090831-soq.sht		

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2744	09-00053-00-RS	LAKE	25	3
FED. ROAD DIST. NO. 1	C-91-891-09	CONTRACT NO. 63338		
		ILLINOIS FED. AID PROJECT ARA-9003(457)		