

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	1000-2A TOTAL QUANTITY	1000-2A 100% FEDERAL 0% LOCAL
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	170	170
25200100	SODDING	SQ YD	170	170
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,400	1,400
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	120	120
40600300	AGGREGATE (PRIME COAT)	TON	28	28
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,170	1,170
42101300	PROTECTIVE COAT	SQ YD	300	300
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	50	50
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	750	750
⊛ 42400800	DETECTABLE WARNINGS	SQ FT	12	12
⊛ 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	13,000	13,000
⊛ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50	50
⊛ 44000600	SIDEWALK REMOVAL	SQ FT	750	750
⊛ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500
⊛ 44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	50	50
⊛ 44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	50	50
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1
⊛ 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	28	28
⊛ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
⊛ 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
⊛ 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
★ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	40	40
★ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,700	4,700
★ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	400	400
★ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	500	500
★ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150
★ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	130	130
★ 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	122	122
⊛ X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	585	585

- ★ DENOTES SPECIALTY ITEM
- ⊛ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

Drawing File: W:\Projects\08009163 - Madison Street LAPP\Summary.dwg Oct 21, 2009 - 4:45pm

HANCOCK ENGINEERING
 Civil Engineers
 Municipal Consultants
 Established 1911

USER NAME -	DESIGNED - CH	REVISED -
PLOT SCALE -	DRAWN - LEV	REVISED -
PLOT DATE -	CHECKED - MDL	REVISED -
	DATE - 08/21/09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS
STA. _____	TO STA. _____

F.A.U. RTE. 1419	SECTION 09-00140-00-RS	COUNTY COOK	TOTAL SHEETS 14	SHEET NO. 3
CONTRACT NO. 63366			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-903(344)	