



**NOTES:**

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

Plotted: October 9, 2009 @ 8:13 AM By: Terri Seidler-Johnson - Tab: 20 TC-22 22x34

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.

**Engineering Enterprises, Inc.**  
 CONSULTING ENGINEERS  
 52 Wheeler Road  
 Sugar Grove, Illinois 60554  
 630.466.6700 / www.eeiweb.com

**CITY OF WARRENVILLE**  
 DUPAGE COUNTY, ILLINOIS

NO.	DATE	REVISIONS

**BATAVIA ROAD**  
 LAPP IMPROVEMENTS

**ARTERIAL ROAD**  
 INFORMATION SIGN  
 TC-22

DATE: OCTOBER 2009  
 PROJECT NO: WV0902  
 FILE: WV0902-CVR  
 SHEET **20** OF **27**

Path: H:\SIS\PROJ\WV0902\DWG\WV0902.DWG FINAL ENG\WV0902-CVR