

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	J000-2A	Y031-1F	Y030-1E	Y007
				ROADWAY	TRAFFIC SIGNALS	LIGHTING	RETAINING WALL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	307	307			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16	16			
20101000	TEMPORARY FENCE	FOOT	2842	2842			
20101200	TREE ROOT PRUNING	EACH	70	70			
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	45	45			
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	25	25			
20200100	EARTH EXCAVATION	CU YD	8945	8945			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1020	1020			
20400800	FURNISHED EXCAVATION	CU YD	740	740			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	123				123
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1020	1020			
20800150	TRENCH BACKFILL	CU YD	747	747			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	20543	20543			
● 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7649	7649			
● 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	141	141			
● 21300010	EXPLORATION TRENCH, SPECIAL	FOOT	550	450		100	
21400100	GRADING AND SHAPING DITCHES	FOOT	200	200			
● 25000300	SEEDING, CLASS 3	ACRE	0.2	0.2			
● 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	130	130			
● 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	121	121			
● 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	116	116			
● 25100630	EROSION CONTROL BLANKET	SQ YD	578	578			
● 25200110	SODDING, SALT TOLERANT	SQ YD	7649	7649			
● 25200200	SUPPLEMENTAL WATERING	UNIT	125	125			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	158	158			
28000510	INLET FILTERS	EACH	133	133			
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	313	313			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3983	3983			
40600300	AGGREGATE (PRIME COAT)	TON	12	12			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	193	193			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	907	907			
40701911	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 11 1/2"	SQ YD	707	707			
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	14900	14900			
42001300	PROTECTIVE COAT	SQ YD	26353	26353			
42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	2148	2148			
●	SPECIALTY ITEM						

FILE NAME = ...oad\sheeta\2215_Sum_Quant.dgn	USER NAME = krk	DESIGNED - JAT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WRIGHT BOULEVARD SUMMARY OF QUANTITIES	F.A.U. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 50.0000' / IN.	CHECKED - DJK	REVISED -	1351			06-00090-00-PV	COOK	137	4	
PLOT DATE = 10/29/2009	DATE - 10-16-09	REVISED -	CONTRACT NO. 63378							
						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-M-8003(809)				
						SHEET NO. 1 OF 8 SHEETS				