

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	J000-2A	Y031-1F	Y030-1E	Y007
				ROADWAY	TRAFFIC SIGNALS	LIGHTING	RETAINING WALL
● 83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	48			48	
● 83600400	POLE FOUNDATION, METAL	EACH	20			20	
● 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	7			7	
● 84200700	LIGHTING FOUNDATION REMOVAL	EACH	7			7	
● 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2			2	
● 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2			2	
● 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2			2	
● 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3		3		
● 85000205	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION (SPECIAL)	EACH	2		2		
● 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2753		2753		
● 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	4697		4697		
● 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1872		1872		
● 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2385		2385		
● 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3594		3594		
● 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	27		27		
● 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT.	EACH	6		6		
● 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	2		2		
● 87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1		1		
● 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1		
● 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		1		
● 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	40		40		
● 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4		
● 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30		30		
● 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		15		
● 87900200	DRILL EXISTING HANDHOLE	EACH	16		16		
● 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1		1		
● 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1		
● 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8		8		
● 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8		8		
● 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	1		1		
● 88500100	INDUCTIVE LOOP DETECTOR	EACH	1		1		
● 88600100	DETECTOR LOOP, TYPE 1	FOOT	941		941		
● 88800100	PEDESTRIAN PUSH-BUTTON	EACH	16		16		

● SPECIALTY ITEM

FILE NAME = ...\\oad\sheeta\2215\_Sum\_Quant.dgn

USER NAME = krk

DESIGNED - JAT  
DRAWN - JAT

REVISED -  
REVISED -

PLOT SCALE = 50,0000' / IN.

CHECKED - DJK

REVISED -

PLOT DATE = 10/29/2009

DATE - 10-16-09

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

WRIGHT BOULEVARD  
SUMMARY OF QUANTITIES

SHEET NO. 6 OF 8 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1351	06-00090-00-PV	COOK	137	9
CONTRACT NO. 63378				
FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT ARA-M-8003(809)				