

SCHEDULE OF QUANTITIES		
PAY ITEM	UNIT	QUANTITY
CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	54
CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	85
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	54
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1093
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1299
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	296
TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT.	EACH	3
CONCRETE FOUNDATION, TYPE A	FOOT	16
DRILL EXISTING HANDHOLE	EACH	4
PEDESTRIAN SIGNAL HEAD, L.E.D, 1-FACE, BRACKET MOUNTED, WITH COUNTDOWN TIMER	EACH	4
PEDESTRIAN SIGNAL HEAD, L.E.D, 2-FACE, BRACKET MOUNTED, WITH COUNTDOWN TIMER	EACH	1
DETECTOR LOOP, TYPE I	FOOT	213
PEDESTRIAN PUSH-BUTTON	EACH	5
RELOCATE EXISTING SIGNAL HEAD	EACH	1
RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1
MODIFY EXISTING CONTROLLER	EACH	1
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	296
REMOVE EXISTING CONCRETE FOUNDATION	EACH	1

NOTE: THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

FILE NAME =	USER NAME = Jat	DESIGNED - BRD	REVISED -	4	SEQUENCES AND SCHEDULE OF QUANTITIES	F.A.U. SECTION	COUNTY TOTAL SHEET SHEETS NO.
J:\2215\cad\sheets\Signals\76_EB_Front@Wr	ght_Sequences&S00.dgn	DRAWN - OJT	REVISED -	STATE OF IL, NOIS	WRIGHT BOULEVARD AT EASTBOUND FRONTAGE ROAD	1351 06~00090-00-PV	COOK 137 76
	PLOT SCALE = 50.0000 '/ IN.	CHECKED - JJE	REVISED -	DEPARTMENT OF TRANSPORTATION	WALIGHT DOOLEVAND AT EASTDOOMD FROMTAGE NOAD		CONTRACT NO. 63378
	PLOT DATE = 10/15/2009	DATE - 10-16-09	REVISED -	N "	SCALE: N.T.S. SHEET NO. 8 OF 25 SHEETS	FED. ROAD DIST. NO. 1 ILLINOIS FEI	D. AID PROJECT ARA-M-8003 (809)