

SCHEDULE OF QUANTITIES		
PAY ITEM	UNIT	QUANTITY
CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	5
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	106
CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	104
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	534
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	827
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	110
TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT.	EACH	2
CONCRETE FOUNDATION, TYPE A	FOOT	12
DRILL EXISTING HANDHOLE	EACH	5
PEDESTRIAN SIGNAL HEAD, L.E.D, 1-FACE, BRACKET MOUNTED, WITH COUNTDOWN TIMER	EACH	2
PEDESTRIAN SIGNAL HEAD, L.E.D, 2-FACE, BRACKET MOUNTED, WITH COUNTDOWN TIMER	EACH	2
DETECTOR LOOP, TYPE I	FOOT	211
PEDESTRIAN PUSH-BUTTON	EACH	4
RELOCATE EXISTING SIGNAL HEAD	EACH	1
RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1
MODIFY EXISTING CONTROLLER	EACH	1
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	110
REMOVE EXISTING CONCRETE FOUNDATION	EACH	1
REBUILD EXISTING HANDHOLE	EACH	1

ME.

NOTE: THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

FILE NAME =	USER NAME = jat	DESIGNED - BRD	REVISED -		SEQUENCES AND SCHEDULE OF QUANTITIES	F.A.U. SECTION	COUNTY	TOTAL SHEET
J:\2215\cad\sheets\Signals\79_W8_Front@W	r ght_Sequences&SB0.dgn	DRAWN - OJT	REVISED -	STATE OF ILLINOIS	WOIGHT BOULEVARD AT WESTBOUND FRONTAGE ROAD	1351 06-00090-00-PV	соок	137 79
	PLOT SCALE = 50.0000 '/ IN.	CHECKED - JJE	REVISED -	DEPARTMENT OF TRANSPORTATION	A A A A A A A A A A A A A A A A A A A			NO. 63378
	PLOT DATE = 10/15/2009	DATE - 10-16-09	REVISED -		SCALE: N.T.S. SHEET NO. 11 OF 25 SHEETS	FED. ROAD DIST. NO. 1 ILLINOIS FED.	AID PROJECT ARA-M	