

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	FEDERAL 100%
			Y007 TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	53
20200100	EARTH EXCAVATION	CU YD	825
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	52
20400800	FURNISHED EXCAVATION	CU YD	585
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	100
* 25000210	SEEDING, CLASS 2A	ACRE	1.00
* 25000310	SEEDING, CLASS 4	ACRE	0.25
;) * 25000750	MOWING	ACRE	1.00
* 25100115	MULCH, METHOD 2	ACRE	1.25
* 25100630	EROSION CONTROL BLANKET	SQ YD	6051
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	375
28000305	TEMPORARY DITCH CHECKS	FOOT	720
28000400	PERIMETER EROSION BARRIER	FOOT	474
28000500	INLET AND PIPE PROTECTION	EACH	4
28100107	STONE RIPRAP, CLASS A4	SQ YD	190
28200200	FILTER FABRIC	SQ YD	190
35101400	AGGREGATE BASE COURSE, TYPE B	TON	416
40600990	TEMPORARY RAMP	SQ YD	52
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	289
44004250	PAVED SHOULDER REMOVAL	SQ YD	61
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	339
48101200	AGGREGATE SHOULDERS, TYPE B	TON	389
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	1715
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1
51205200	TEMPORARY SHEET PILING	SQ FT	569
51500100	NAME PLATES	EACH	2
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	102
54200475	PIPE CULVERTS, TYPE 1 RCCP 60"	FOOT	82
54207615	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 60"	FOOT	120
54213450	END SECTIONS 15"	EACH	4
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	2

* SPECIALTY ITEM
;) NON-PARTICIPATING 100% STATE