SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION	OFFSET (FT.)	UNIT	REMARKS
STA 969+24	58' LT	6	MEYER ROAD
STA 969+24	58' LT	6	MEYER ROAD
STA 969+24	58' LT	7	MEYER ROAD
STA 969+24	58' LT	6	MEYER ROAD
STA 969+24	58' LT	7	MEYER ROAD
STA 969+24	58' LT	8	MEYER ROAD
STA 969+24	58' LT	7	MEYER ROAD
STA 969+24	58' LT	6	MEYER ROAD
	TOTAL	53	

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

LOCATION	CU YD	REMARKS
STA 969 + 28.62	52	MEYER ROAD
TOTAL	52	

20400800 FURNISHED EXCAVATION

LOCATION			CU YD	REMARKS
STA 895 + 00	TO	STA 900 + 50	345	CHELSEA ROAD
STA 966 + 50	TO	STA 972 + 25.07	240	MEYER ROAD
		TOTAL	585	

25000210 SEEDING, CLASS 2A

LOCATION				ACRE	REMARKS
STA 895 + 00	TO	STA 900 + 50	LT	0.25	CHELSEA ROAD
STA 895 + 00	TO	STA 900 + 50	RT	0.25	CHELSEA ROAD
STA 966 + 50	TO	STA 972 + 25.07	LT	0.20	MEYER ROAD
STA 966 + 50	TO	STA 972 + 25.07	RT	0.30	MEYER ROAD
			TOTAL	1.00	

25000310 SEEDING, CLASS 4

LOCATION				ACRE	REMARKS
STA 895 + 00	TO	STA 900 + 50	LT	0.05	CHELSEA ROAD
STA 895 + 00	TO	STA 900 + 50	RT	0.08	CHELSEA ROAD
STA 966 + 50	TO	STA 972 + 25.07	LT	0.07	MEYER ROAD
STA 966 + 50	TO	STA 972 + 25.07	RT	0.05	MEYER ROAD
			TOTAL	0.25	

25000750 MOWING

LOCATION				ACRE	REMARKS
STA 895 + 00	TO	STA 900 + 50	LT	0.25	CHELSEA ROAD
STA 895 + 00	TO	STA 900 + 50	RT	0.25	CHELSEA ROAD
STA 966 + 50	TO	STA 972 + 25.07	LT	0.20	MEYER ROAD
STA 966 + 50	TO	STA 972 + 25.07	RT	0.30	MEYER ROAD
			TOTAL	1.00	

25100115 MULCH, METHOD 2

LOCATION				ACRE	REMARKS
STA 895 + 00	TO	STA 900 + 50	LT	0.30	CHELSEA ROAD
STA 895 + 00	TO	STA 900 + 50	RT	0.33	CHELSEA ROAD
STA 966 + 50	TO	STA 972 + 25.07	LT	0.27	MEYER ROAD
STA 966 + 50	TO	STA 972 + 25.07	RT	0.35	MEYER ROAD
			TOTAL	1.25	

25100630 EROSION CONTROL BLANKET

LOCATION				SQ YD	REMARKS
STA 895 + 00	TO	STA 900 + 50	LT	1452	CHELSEA ROAD
STA 895 + 00	TO	STA 900 + 50	RT	1598	CHELSEA ROAD
STA 966 + 50	TO	STA 972 + 25.07	LT	1307	MEYER ROAD
STA 966 + 50	TO	STA 972 + 25.07	RT	1694	MEYER ROAD
			TOTAL	6051	

28000250 TEMPORARY EROSION CONTROL SEEDING

LOCATION			POUND	REMARKS
STA 895 + 00	TO	STA 900 + 50	63	CHELSEA ROAD
STA 966 + 50	TO	STA 972 + 25.07	62	MEYER ROAD
			125	
		TOTAL	375	3 APPLICATIONS

28000305 TEMPORARY DITCH CHECKS

LOCATION				FOOT	REMARKS
STA 895 + 00	TO	STA 900 + 50	LT	105	CHELSEA ROAD
STA 895 + 00	TO	STA 900 + 50	RT	195	CHELSEA ROAD
STA 966 + 50	TO	STA 972 + 25.07	LT	195	MEYER ROAD
STA 966 + 50	TO	STA 972 + 25.07	RT	225	MEYER ROAD
			TOTAL	720	

28000400 PERIMETER EROSION BARRIER

LOCATION				FOOT	REMARKS
STA 895 + 50	TO	STA 896 + 50	RT	101	CHELSEA ROAD
STA 898 + 44.89	TO	STA 900 + 50	LT	209	CHELSEA ROAD
STA 968 + 00	TO	STA 969 + 50	RT	164	MEYER ROAD
			TOTAL	474	

28000500 INLET AND PIPE PROTECTION

LOCATION		EACH	REMARKS
STA 896 + 74.95	LT	1	CHELSEA ROAD
STA 897 + 77.46	RT	1	CHELSEA ROAD
STA 967 + 65.95	LT	1	MEYER ROAD
STA 969 + 28.62	LT	1	MEYER ROAD
	TOTAL	4	

28100107 STONE RIPRAP, CLASS A4

LOCATION		SQ YD	REMARKS
STA 897 + 77.46	LT	117	CHELSEA ROAD
STA 897 + 77.46	RT	40	CHELSEA ROAD
STA 969 + 28.62	RT	33	MEYER ROAD
	TOTAL	190	

28200200 FILTER FABRIC

LOCATION		SQ YD	REMARKS
STA 897 + 77.46	LT	117	CHELSEA ROAD
STA 897 + 77.46	RT	40	CHELSEA ROAD
STA 969 + 28.62	RT	33	MEYER ROAD
	TOTAL	190	