

CODE #	ITEM	UNIT	URBAN TOTAL QUANTITY	STP (L20) CONSTRUCTION TYPE CODE BRF (L1C)	
				80% FEDERAL 20% STATE ROADWAY J000	80% FEDERAL 20% STATE BRIDGE X081-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	996	996	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	130	130	
20200100	EARTH EXCAVATION	CU YD	5250	5250	
20300100	CHANNEL EXCAVATION	CU YD	701	701	
20400100	BORROW EXCAVATION	CU YD	22	22	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	375		375
20800150	TRENCH BACKFILL	CU YD	105	105	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6050	6050	
* 25000210	SEEDING, CLASS 2A	ACRE	1.25	1.25	
*† 25000750	MOWING	ACRE	1.25	1.25	
* 25100115	MULCH, METHOD 2	ACRE	1.25	1.25	
* 25100630	EROSION CONTROL BLANKET	SQ YD	929	929	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	500	500	
28000305	TEMPORARY DITCH CHECKS	FOOT	543	543	
28000400	PERIMETER EROSION BARRIER	FOOT	204	204	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100105	STONE RIPRAP, CLASS A3	SQ YD	115	115	
28100109	STONE RIPRAP, CLASS A5	SQ YD	1053		1053
28200200	FILTER FABRIC	SQ YD	1168	115	1053
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	7660	7660	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	118	118	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	186	186	
40600990	TEMPORARY RAMP	SQ YD	331	331	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	110	110	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	34	34	
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	3787	3787	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1647	1647	
44000100	PAVEMENT REMOVAL	SQ YD	5347	5347	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	938	938	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	47	47	
44003100	MEDIAN REMOVAL	SQ FT	1549	1549	
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1549	1549	
44000700	APPROACH SLAB REMOVAL	SQ YD	290	290	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	27	27	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	186	186	
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SQ YD	1088	1088	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	124		124

* SPECIALTY ITEM
† NON-PARTICIPATING
100% STATE

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
#FILE#		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	742	34BR-1	WINNEBAGO	78	3
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -						CONTRACT NO. 64E68						
	PLOT DATE = #DATE#	DATE -	REVISED -						ILLINOIS FED. AID PROJECT						