

28000400 PERIMETER EROSION BARRIER	40603335 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	44003510 MEDIAN REMOVAL PARTIAL DEPTH	54215547 METAL END SECTIONS 12"
FOOT LOCATION	TON LOCATION	SQ FT LOCATION	EACH LOCATION
204 STA. 218+00 TO STA 220+00 LT STAGE 1	110 STA. 214+74.47 TO STA 218+02.62	1549 STA. 208+64.3 TO STA. 212+46.1 PRE-STAGE 1	1 STA. 215+59.4 RT
204 TOTAL	110 TOTAL	1549 TOTAL	1 STA. 215+59.4 LT
28000500 INLET AND PIPE PROTECTION	40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING	44000700 APPROACH SLAB REMOVAL	550A0340 STORM SEWERS, CLASS A, TYPE 2 12"
EACH LOCATION	TON LOCATION	SQ YD LOCATION	FOOT LOCATION
1 STA. 213+05 LT STAGE 1	34 STA. 213+06.5 TO STA 214+25.5	146 STA. 215+99 TO STA. 216+19	332 SEE TABLE IN PP SHEET
1 TOTAL	34 TOTAL	144 STA. 216+58 TO STA. 216+78	332 TOTAL
28100105 STONE RIPRAP, CLASS A3	42000411 PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	44201761 CLASS D, TYPE I, 10 INCH	55100500 STORM SEWER REMOVAL 12"
SQ YD LOCATION	SQ YD LOCATION	SQ YD LOCATION	FOOT LOCATION
115 STA. 215+00 RT STAGE 2	1574 STA. 210+43.79 TO STA. 214+67.27 LT	9 STA. 210+82 RT	152 STA. 210+82 TO 212+35
115 TOTAL	1123 STA. 210+43.79 TO STA. 214+67.27 RT	9 STA. 212+35 RT	152 TOTAL
28200200 FILTER FABRIC	1091 STA. 218+06 TO STA. 219+45.6LT & RT	9 STA. 208+75 RT	55100700 STORM SEWER REMOVAL 15"
SQ YD LOCATION	3787 TOTAL	27 TOTAL	FOOT LOCATION
115 STA. 215+00 RT STAGE 2	42001420 BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	48101200 AGGREGATE SHOULDERS, TYPE B 9 1/2"	46 STA. 212+35 RT
115 TOTAL	SQ YD LOCATION	TON LOCATION	46 TOTAL
31100910 SUB-BASE GRANULAR MATERIAL, TYPE A 12"	397 STA. 214+67.3 TO STA. 215+67.3 LT	57 STA. 210+43.8 TO STA. 213+10.6 LT	60100060 CONCRETE HEADWALL FOR PIPE DRAINS
SQ YD LOCATION	393 STA. 214+67.3 TO STA. 215+67.3 RT	24 STA. 213+96 TO STA. 215+52.3 LT	EACH LOCATION
5051.2 SOUTH OF BRIDGE	427 STA. 217+06.02 TO STA. 218+06.03 LT	16 STA. 217+21 TO STA. 219+45.61 LT	2 STA. 213+59.9 RT
2608.8 NORTH OF BRIDGE	430 STA. 217+06.02 TO STA. 218+06.03 RT	73 STA. 210+43.8 TO STA. 214+10.00 RT	2 STA. 213+95.7 RT
7660.0 TOTAL	1647 TOTAL	17 STA. 217+21 TO STA. 218+82.2 RT	1 STA. 217+16.02 RT
35101400 AGGREGATE BASE COURSE, TYPE B	44000100 PAVEMENT REMOVAL	186 TOTAL	1 STA. 217+06.02 LT
TON LOCATION	SQ YD LOCATION	48300410 PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	6 TOTAL
118 STA. 213+42 LT C.E.	3810 STA. 210+43.79 TO STA. 215+99 LT & RT	SQ YD LOCATION	60100945 PIPE DRAINS 12"
118 TOTAL	1537 STA. 216+78 TO STA. 219+45.6LT & RT	328 STA. 210+43.78 TO STA. 214+67.27 LT	FOOT LOCATION
40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	5347 TOTAL	493 STA. 210+43.78 TO STA. 214+67.27 RT	32 STA. 215+59.4 RT
SQ YD LOCATION	44000152 HOT MIX ASPHALT SURFACE REMOVAL, 3/4"	182 STA. 218+06 TO STA. 219+45.61 LT	30 STA. 215+59.4 LT
102 STA. 214+74.47 TO STA. 214+99.47 RT	SQ YD LOCATION	82 STA. 218+06 TO STA. 218+82.2 RT	62 TOTAL
84 STA. 217+77.62 TO STA. 218+02.62 RT	938 STA. 214+99.47 TO STA. 217+77.62 LT & RT	3 STA. 219+38 TO STA. 219+45.61 RT	60107600 PIPE UNDERDRAINS 4"
186 TOTAL	938 TOTAL	1088 TOTAL	FOOT LOCATION
40600990 TEMPORARY RAMP	44000500 COMBINATION CURB AND GUTTER REMOVAL	542D1060 PIPE CULVERTS, CLASS D, TYPE 2 15"	311 STA. 210+44 TO STA. 213+60 RT
SQ YD LOCATION	FOOT LOCATION	FOOT LOCATION	192 STA. 213+60 TO STA. 215+52 RT
179 STA. 214+74.47 TO STA 215+19.47	22 STA. 218+94 TO STA. 218+94 RT	58 STA. 213+42 LT	84 STA. 213+11 TO STA. 213+96 LT
152 STA. 217+57.62 TO STA 218+02.62	25 STA. 219+23 TO STA. 219+23 RT	58 TOTAL	156 STA. 213+96 TO STA. 215+52 LT
331 TOTAL	47 TOTAL	54213450 END SECTION 15"	230 STA. 217+06 TO STA. 219+46 LT
44003100 MEDIAN REMOVAL	44003100 MEDIAN REMOVAL	FOOT LOCATION	150 STA. 217+16 TO STA. 218+66 RT
SQ FT LOCATION	SQ FT LOCATION	1 STA. 213+13.5 LT	1123 TOTAL
1549 STA. 208+64.3 TO STA. 212+46.1 STAGE 3	1549 STA. 208+64.3 TO STA. 212+46.1 STAGE 3	1 STA. 213+71.3 LT	
1549 TOTAL	1549 TOTAL	2 TOTAL	
		54213657 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	
		EACH LOCATION	
		1 STA. 212+11 RT	
		1 STA. 213+95 RT	
		2 TOTAL	

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	WINNEBAGO	78	8
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -								CONTRACT NO. 64E68		
	PLOT DATE = #DATE#	DATE -	REVISED -								ILLINOIS FED. AID PROJECT		