78008210 POLYUREA PAVEMENT MARKING TYPE I - LINE 4"

FOOT	LOCATION								
267	STA	21044	TO	STA	21311	LT	WHITE	EDGE OF LANE	
1024	STA	21311	TO	STA	22335	LT	WHITE	EDGE OF LANE	
884	STA	22391	TO	STA	23275	LT	WHITE	EDGE OF LANE	
50	STA	23809	TO	STA	24000	LT	WHITE	℄ OF LANES (10'/40')	
50	STA	20848	TO	STA	21044	LT	WHITE	℄ OF LANES (10'/40')	
110	STA	21044	TO	STA	21467	LT	WHITE	℄ OF LANES (10'/40')	
80	STA	21467	TO	STA	21806	LT	WHITE	℄ OF LANES (10'/40')	
40	STA	21806	TO	STA	21946	LT	WHITE	℄ OF LANES (10'/40')	
670	STA	21946	TO	STA	24615	LT	WHITE	℄ OF LANES (10'/40')	
241	STA	21567	TO	STA	21808	LT	YELLOW	SOLID	
148	STA	21808	TO	STA	21882	LT	YELLOW	DOUBLE	
389	STA	21946	TO	STA	22335	LT	YELLOW	SOLID	
465	STA	22391	TO	STA	22856	LT	YELLOW	SOLID	
378	STA	22913	TO	STA	23291	LT	YELLOW	SOLID	
152	STA	21806	TO	STA	21882	RT	YELLOW	DOUBLE	
239	STA	21567	TO	STA	21806	RT	YELLOW	SOLID	
389	STA	21946	TO	STA	22335	RT	YELLOW	SOLID	
465	STA	22391	TO	STA	22856	RT	YELLOW	SOLID	
378	STA	22913	TO	STA	23291	RT	YELLOW	SOLID	
1400	STA	23291	TO	STA	24691	RT	YELLOW	SOLID	
40	STA	20871	TO	STA	21044	RT	WHITE	℄ OF LANES (10'/40')	
110	STA	21044	TO	STA	21467	RT	WHITE	℄ OF LANES (10'/40')	
80	STA	21467	TO	STA	21806	RT	WHITE	℄ OF LANES (10'/40')	
40	STA	21806	TO	STA	21946	RT	WHITE	℄ OF LANES (10'/40')	
690	STA	21946	TO	STA	24691	RT	WHITE	℄ OF LANES (10'/40')	
852	STA	21044	TO	STA	21896	RT	WHITE	EDGE OF LANE	
168	STA	21923	TO	STA	22091	RT	WHITE	EDGE OF LANE	
275	STA	1535	TO	STA	1810	LT	WHITE	EDGE OF LANE	BELTLINE
230	STA	1005	TO	STA	1917	LT	WHITE	℄ OF LANES (10'/40')	BELTLINE
1140	STA	1306	TO	STA	1876	LT	YELLOW	DOUBLE	BELTLINE
288	STA	1162	TO	STA	1306	LT	YELLOW	DOUBLE	BELTLINE
366	STA	1503	TO	STA	1686	LT	YELLOW	DOUBLE	BELTLINE
994	STA	1006	TO	STA	1503	RT	YELLOW	DOUBLE	BELTLINE
370	STA	398	TO	STA	1891	RT	WHITE	℄ OF LANES (10'/40')	BELTLINE
607	STA	398	TO	STA	1005	RT	WHITE	EDGE OF LANE	BELTLINE

14069 TOTAL

78008240 POLYUREA PAVEMENT MARKING TYPE I - LINE 8"

FOOT	LOCATION								
628	STA	234+26	TO	STA	240+54	LT	WHITE	OUTSIDE OF RAMP	
52	STA	240+00	TO	STA	240+52	LT	WHITE	INSIDE OF RAMP	
276	STA	207+67	TO	STA	210+43	LT	WHITE	LANE DIVIDE	
68	STA	210+43	TO	STA	211+11	LT	WHITE	LANE DIVIDE	
50	STA	211+11	TO	STA	213+11	LT	WHITE	SKIP DASH (2'/6')	
196	STA	208+48	TO	STA	210+44	LT	WHITE	LANE DIVIDE	
67	STA	210+44	TO	STA	211+11	LT	WHITE	LANE DIVIDE	
50	STA	211+11	TO	STA	213+11	LT	WHITE	SKIP DASH (2'/6')	
156	STA	1006	TO	STA	1162	LT	WHITE	LANE DIVIDE	BELTLINE
36	STA	1162	TO	STA	1306	LT	WHITE	SKIP DASH (2'/6')	BELTLINE
205	STA	1686	TO	STA	1891	RT	WHITE	LANE DIVIDE	BELTLINE
46	STA	1503	TO	STA	1686	RT	WHITE	SKIP DASH (2'/6')	BELTLINE
78	STA	1797	TO	STA	1875	RT	WHITE	LANE DIVIDE	BELTLINE

1908 TOTAL

78008250 POLYUREA PAVEMENT MARKING TYPE I - LINE 12"

FOOT	LOCATION						
67	STA	218+06	TO	STA	218+82	MEDIAN	YELLOW @ 45
32	STA	219+23	TO	STA	223+35	MEDIAN	YELLOW @ 45
32	STA	229+13	TO	STA	232+91	MEDIAN	YELLOW @ 45
322	STA	212+11	TO	STA	219+46	LT	WHITE @ 45
405	STA	210+44	TO	STA	218+82	RT	WHITE @ 45
240	STA	1162	TO	STA	1686	MEDIAN	YELLOW @ 45

1098 TOTAL

78008270 POLYUREA PAVEMENT MARKING TYPE I - LINE 24"

FOOT	LOCATION	
24	SB THRU LANE	STOP BAR
12	SB LT TURN	STOP BAR
12	NB LT TURN	STOP BAR
24	NB THRU LANE	STOP BAR

72 TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION						
2	STA	210+43	TO	STA	211+11	LT	LANE DIVIDE @ 40'
5	STA	210+44	TO	STA	214+67	LT	℄ OF LANES @ 80'
2	STA	218+06	TO	STA	219+46	LT	℄ OF LANES @ 80'
2	STA	210+44	TO	STA	211+11	LT	LANE DIVIDE @ 40'
2	STA	218+08	TO	STA	218+82	LT	DOUBLE YELLOW @ 40'
2	STA	218+06	TO	STA	218+82	RT	DOUBLE YELLOW @ 40'
5	STA	210+44	TO	STA	214+67	RT	℄ OF LANES @ 80'
4	STA	218+06	TO	STA	219+46	RT	℄ OF LANES @ 80'

24 TOTAL

78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)

EACH	LOCATION						
4	STA	214+67	TO	STA	218+06	LT	℄ OF LANES @ 80'
6	STA	215+67	TO	STA	218+08	LT	YELLOW LINE @ 40'
6	STA	215+67	TO	STA	218+06	RT	YELLOW LINE @ 40'
4	STA	214+67	TO	STA	218+06	RT	℄ OF LANES @ 80'

20 TOTAL

78100300 REPLACEMENT REFLECTOR

EACH	LOCATION							
31	STA	234+26	TO	STA	240+54	LT	OUTSIDE OF RAMP @ 20'	
1	STA	240+00	TO	STA	240+52	LT	INSIDE OF RAMP @ 40'	
5	STA	207+67	TO	STA	210+43	LT	LANE DIVIDE @ 40'	
2	STA	238+09	TO	STA	240+00	LT	℄ OF LANES @ 80'	
2	STA	208+48	TO	STA	210+44	LT	℄ OF LANES @ 80'	
33	STA	219+46	TO	STA	246+15	LT	℄ OF LANES @ 80'	
5	STA	208+48	TO	STA	210+44	LT	LANE DIVIDE @ 40'	
4	STA	219+46	TO	STA	223+35	LT	YELLOW @ 40'	
11	STA	223+91	TO	STA	228+56	LT	YELLOW @ 40'	
9	STA	229+13	TO	STA	232+91	LT	YELLOW @ 40'	
7	STA	219+46	TO	STA	223+35	RT	YELLOW @ 40'	
12	STA	223+91	TO	STA	228+56	RT	YELLOW @ 40'	
9	STA	229+13	TO	STA	232+91	RT	YELLOW @ 40'	
2	STA	208+71	TO	STA	210+44	RT	℄ OF LANES @ 80'	
21	STA	219+46	TO	STA	246+91	RT	℄ OF LANES @ 80'	
11	STA	1005	TO	STA	1917	LT	℄ OF LANES @ 80'	BELTLINE
4	STA	1006	TO	STA	1162	LT	LANE DIVIDE @ 40'	BELTLINE
14	STA	1306	TO	STA	1876	LT	DBLE YELLOW @ 40'	BELTLINE
4	STA	1162	TO	STA	1306	LT	DBLE YELLOW @ 40'	BELTLINE
5	STA	1503	TO	STA	1686	LT	DBLE YELLOW @ 40'	BELTLINE
12	STA	1006	TO	STA	1503	RT	DBLE YELLOW @ 40'	BELTLINE
5	STA	1686	TO	STA	1891	RT	LANE DIVIDE @ 40'	BELTLINE
19	STA	398	TO	STA	1891	RT	℄ OF LANES @ 80'	BELTLINE
2	STA	1797	TO	STA	1875	RT	LANE DIVIDE @ 40'	BELTLINE

230 TOTAL

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION					
4	STA. 214+89.1	TO	STA.	215+82.3	LT
4	STA. 216+91.0	TO	STA.	218+59.2	LT
4	STA. 214+14.1	TO	STA.	215+82.3	RT
4	STA. 216+91.0	TO	STA.	217+84.2	LT

16 TOTAL

78200520 BARRIER WALL MARKERS, TYPE B

EACH	LOCATION
4	LT SIDE BRIDGE
4	RT SIDE BRIDGE

8 TOTAL

78201000 TERMINAL MARKER-DIRECT APPLIED

EACH	LOCATION	
1	STA. 214+89.1	LT
1	STA. 218+59.2	LT
1	STA. 214+14.1	RT
1	STA. 217+84.2	RT

4 TOTAL

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			742	34BR-1	WINNEBAGO	78	12
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -					CONTRACT NO. 64E68		
	PLOT DATE = $DATE$	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			