

IL 75 SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% Federal	1000	1000	RURAL
			TOTAL QUANTITY	RURAL	URBAN	101-1085 101-1084
40600525	LEVELING BINDER (HAND METHOD), N50	TON	55	44.0	11.0	
40600625	LEVEL BINDER (MACHINE METHOD), N50	TON	5659	4679.0	980.0	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1.0		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	1928	959.0	969.0	
40600990	TEMPORARY RAMP	SQ YD	202	91.0	111.0	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	498	422.0	76.0	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	7983	6282.0	1470.0	231.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1360	1040.0	320.0	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	115		115.0	
42400800	DETECTABLE WARNINGS	SQ FT	9		9.0	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	959		959.0	
44000400	GUTTER REMOVAL	FOOT	1001	1001.0		
44000600	SIDEWALK REMOVAL	SQ FT	213		213.0	
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	2543	2154.0	389.0	
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	479			479.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	77	50.0	27.0	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	50	35.0	15.0	
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	2701	2587.0	114.0	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	49978	38670.0	11308.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	486	127.0		359.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2684	2420.0	264.0	
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	1654			1654.0
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1.0
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1.0
50102400	CONCRETE REMOVAL	CU YD	8.40	8.4		
50105200	REMOVE EXISTING CULVERTS	EACH	2			2.0
50800105	REINFORCEMENT BARS	POUND	19440			19440.0