

HORIZONTAL CONTROL POINTS							
POINT	NORTH	EAST	ELEVATION	CHAIN	STATION	OFFSET	DESCRIPTION
1	2102089.7840	2579767.2660	741.1040	EXIL75	789+75.25	18.6301' RT	GPS CONTROL POINT, PIN
2	2102514.5330	2580438.2950	748.4940	EXIL75	797+68.51	19.1358' LT	GPS CONTROL POINT, PIN
3	2104888.6620	2583514.2540	739.8890	EXIL75	836+63.68	20.5209' LT	GPS CONTROL POINT, PIN
4	2104942.9840	2584310.5630	738.1500	EXIL75	844+58.91	16.2615' RT	GPS CONTROL POINT, PIN
5	2105384.9110	2585361.4020	756.3990	EXIL75	855+98.04	31.8182' LT	GPS CONTROL POINT, PIN
6	2098737.3808	2566409.3174	730.6785	EXIL75	643+59.10	41.9853' LT	GPS CONTROL POINT, DISK
7	2098976.8199	2564589.4468	732.7068	EXIL75	625+24.70	39.2482' RT	GPS CONTROL POINT, DISK
8	2099082.2534	2564316.7734	731.1307	EXIL75	622+39.16	24.0664' LT	GPS CONTROL POINT, PIN
9	2106983.1241	2563689.9345	828.6870	EXIL75	604+57.72	7746.9659' LT	GPS CONTROL POINT, PIN
10	2107207.2980	2564256.8068	820.4352	EXIL75	609+85.49	8052.0331' LT	GPS CONTROL POINT, PIN
68697285	2100026.7970	2579515.2300	766.6790	EXIL75	777+36.89	1687.7368' RT	NGS MONUMENT, PERM. SURVEY MARKER
65709298	2099342.9107	2562202.6085	733.5290	EXIL75	601+09.64	28.8838' RT	NGS MONUMENT, PERM. SURVEY MARKER

FILE NAME =	USER NAME = goffjl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>HORIZONTAL &amp; VERTICAL CONTROL IL 75</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\goffjl\0142202\004309\hvc.dgn		DRAWN -	REVISED -			505	115RS-2	WINNEBAGO	120	20	
PLOT SCALE = 500.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64E89					
PLOT DATE = Fri Oct 09 12:00:53 2009		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. OF SHEETS		STA. TO STA.			