

IL 75 SCHEDULE OF QUANTITIES

40600990 TEMPORARY RAMP

LOCATION	TON	REMARK	SQ YD	REMARK
RURAL				
STA. 645+74	14.4	BEGIN CONST		
STA. 697+66	11.7	Bates Rd		
STA. 739+67	19.4	Gummow Rd		
STA. 788+03	15.0	Owen Center Rd		
STA. 850+84	16.7	Rockton Ave		
STA. 859+06	13.3	Quail Ridge Close		
	90.6			
URBAN				
STA. 911+93	14.4	S. School Blvd		
STA. 920+16	22.8	Village Wood Lane		
STA. 926+24	15.6	Old River Rd		
STA. 931+19 LT	30.0	River St		
STA. 931+19 RT	13.3	River St		
STA. 934+27	14.4	END CONST		
	110.6			
			201.1	

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

LOCATION	TON	REMARK
RURAL		
STA 791+50 - 796+00 LT	14	Shoulder
STA 791+50 - 796+00 RT	14	Shoulder
STA 840+60 - 850+00 LT	117	Shoulder
STA 840+60 - 850+00 RT	86	Shoulder
	231	

40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING

LOCATION	TON	REMARK
MERIDIAN ROAD & IL 75		
RURAL		
STA. 700+00 - 702+68 RT	107.0	5" Thickness
STA. 700+37 - 700+88 LT	46.0	5" Thickness
MERIDIAN ROAD & SHIRLAND		
STA. 598+12 - 599+64 LT	36.0	5" Thickness
STA. 599+35 - 600+25 RT	25.0	5" Thickness
URBAN		
UNION STREET & IL 75		
STA. 89+21 - 89+88	22.0	5" Thickness
	236	

42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH

LOCATION	SQ FT	REMARKS
URBAN		
UNION STREET & IL 75		
STA. 89+55 - 89+74 LT	115	
	115	

TOTAL

28000305 TEMPORARY DITCH CHECKS

LOCATION	EQT	REMARK
RURAL		
STA. 791+50 - 796+00 LT&RT	110.0	
STA. 840+50 - 850+00 RT	40.0	
	150	

28000400 PERIMETER EROSION BARRIER

LOCATION	EQT	REMARK
RURAL		
STA. 793+00 - 794+00 RT	119.0	
STA. 841+50 - 845+80 RT	435.0	
STA. 847+50 - 849+00 RT	149.0	
STA. 847+35 - 849+16 LT	203.0	
	906	

28000500 INLET AND PIPE PROTECTION

LOCATION	EACH	REMARK
RURAL		
STA. 781+92 RT	1	
STA. 794+38 RT	1	
STA. 793+60 RT	1	
STA. 843+43 RT	1	
STA. 844+66 RT	1	
STA. 846+92 RT	1	
STA. 847+42 LT	1	
	7	

31100910 SUB-BASE GRANULAR MATERIAL, TYPE A 12"

LOCATION	SQ YD	REMARK
RURAL		
MERIDIAN ROAD & IL 75		
STA. 700+00 - 702+68 RT	383	
STA. 700+37 - 700+88 LT	165	
MERIDIAN ROAD & SHIRLAND		
STA. 598+12 - 599+64 LT	130	
STA. 599+35 - 600+25 RT	88	
URBAN		
UNION STREET & IL 75		
STA. 89+21 - 89+88 LT	79	
	845	

35101400 AGGREGATE BASE COURSE TYPE B

LOCATION	TON	REMARK
RURAL		
STA. 794+13 RT	88	FE 8" Thickness
STA. 841+33 LT	55	PE Reconstruct 8" Thickness
STA. 843+62 RT	26	PE Reconstruct 8" Thickness
STA. 844+88 RT	41	PE Reconstruct 8" Thickness
STA. 845+60 LT	31	MB Reconstruct
STA. 847+25 RT	14	PE Reconstruct 8" Thickness
STA. 848+59 LT	31	MB Reconstruct
STA. 848+59 LT	45	PE Reconstruct
STA. 849+32 RT	128	Side Road 12" Thickness
STA. 849+60 LT	25	PE Reconstruct 8" Thickness
	484	

35600716 HOT-MIX ASPHALT BASE COURSE WIDENING 10"

LOCATION	SQ YD	REMARK
RURAL		
STA. 843+21 - 850+46 LT	161	
	161	

40600525 LEVELING BINDER (HAND METHOD), N50

LOCATION	TON	REMARKS
RURAL		
STA. 645+74 - 878+00	44	As needed by the RE
URBAN		
STA. 878+00 - 934+27	11	
	55	

40600625 LEVEL BINDER (MACHINE METHOD), N50

LOCATION	TON	REMARKS
RURAL		
STA. 840+60 - 850+00 LT&RT	913	For Super Correction
	913	

40600982 HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT

LOCATION	SQ YD	REMARKS
RURAL		
STA. 645+74	72	BEGIN CONST
	887	From Side Road Schedule
URBAN		
STA. 934+27	72	END CONST
Side Roads	897	From Side Road Schedule
	1928	

TOTAL

1928