

IL 75 SCHEDULE OF QUANTITIES

42400800 DETECTABLE WARNINGS

LOCATION	SO FT	REMARKS
URBAN UNION STREET & IL 75 STA. 89+60 RT	9	
TOTAL	9	

44000158 HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4"

LOCATION	SO YD	REMARKS
URBAN AT WAGON WHEEL ROAD STA 902+33 - 905+65 LT&RT	959	
TOTAL	959	

44000400 GUTTER REMOVAL

LOCATION	FOOT	REMARKS
RURAL STA. 843+21 - 850+46 Lt	725	
MERIDIAN ROAD & IL 75 STA. 700+24 - 700+62 LT STA. 700+04 - 700+64 RT	67 90	
MERIDIAN ROAD & SHIRLAND STA. 599+59 - 600+02 RT STA. 599+39 - 599+65 LT	60 59	
TOTAL	1001	

44000600 SIDEWALK REMOVAL

LOCATION	SO FT	REMARKS
URBAN UNION STREET & IL 75 STA. 89+55 - 89+86 LT	213	
TOTAL	213	

44201383 CLASS C PATCH, TYPE IV, 12"

LOCATION	SO YD	REMARKS
RURAL STA 793+28 - 793+90 STA 846+04 - 847+08	179 300	
TOTAL	479	

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

LOCATION	FOOT	REMARK
RURAL STA. 645+74 - 697+19 Lt & Rt STA. 736+10 - 878+00 Lt & Rt	10290 28380	
URBAN STA. 878+00 - 934+54 Lt & Rt	38670 11308	
TOTAL	49978	

48101200 AGGREGATE SHOULDERS, TYPE B

LOCATION	ION	REMARK
RURAL STA 791+50 - 796+00 LT STA 791+50 - 796+00 RT STA 841+55 - 844+06 LT STA 840+60 -0843+42 RT	115 115 58 71	8" 8" 8" 8"
MERIDIAN ROAD & IL 75 STA. 700+00 - 702+68 RT STA. 700+37 - 700+78 LT	53 24	6" 6"
MERIDIAN ROAD & SHIRLAND STA. 598+12 - 599+64 LT STA. 599+92 - 600+25 RT	39 11	6" 6"
TOTAL	486	

48102100 AGGREGATE WEDGE SHOULDERS, TYPE B

LOCATION	ION	REMARK
RURAL STA. 645+74 - 878+00 Lt & Rt	2169	3' Wedge
URBAN STA. 878+00 - 906+31 Lt & Rt	264 264	3' Wedge
TOTAL	2433	

48203019 HOT-MIX ASPHALT SHOULDERS, 5-1/2"

LOCATION	SO YD	REMARK
RURAL STA 791+50 - 796+00 LT STA 791+50 - 796+00 RT STA 840+60 - 850+00 LT STA 840+60 - 850+00 RT	100 100 837 617	
TOTAL	1654	

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

LOCATION	EACH	REMARK
RURAL STA 793+60 LT & RT	1	Double 9x4 with Headwals 42' long
TOTAL	1	

50105200 REMOVE EXISTING CULVERTS

LOCATION	EACH	REMARK
RURAL STA 794+13 RT STA 847+22 LT	1 1	
TOTAL	2	

51500100 NAME PLATES

LOCATION	EACH	REMARK
RURAL STA. 793+60	1	
TOTAL	1	

54010603 PRECAST CONCRETE BOX CULVERT 6' X 3'

LOCATION	FOOT	REMARK
RURAL STA 793+60 LT & RT	224	Four cell each 56' long
TOTAL	224	

54200220 PIPE CULVERTS CLASS D, TYPE 1, 15"

LOCATION	FOOT	REMARKS
RURAL STA. 843+62 RT STA. 844+88 RT	52 48	
TOTAL	100	

54200223 PIPE CULVERTS CLASS D, TYPE 1, 18"

LOCATION	FOOT	REMARKS
RURAL STA. 793+13 RT STA. 846+25 - 846+81 RT STA. 847+25 LT	50 56 40	
TOTAL	146	

FILE NAME =	USER NAME = nicklausie	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 75 SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca\p\work\KXP\DOT\NICKLAUSIE\d8142202\44389evr.dgn	PLOT SCALE = 185.5966' / IN.	DRAWN - ---	REVISED - ---			505	11585-2	WINNEBAGO	120	32	
PLOT DATE = Thu Nov 12 13:51:48 2009	DATE - ---	CHECKED - ---	REVISED - ---			CONTRACT NO. 64E89					
						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					