

LOCATION OF WORK:

FAS 1517
 BRIDGE
 SN 074-0086
 STA. 288+40.38
 TO
 STA. 290+04.38
 FED 80%
 STATE 20%
 I000-2A

CONSTRUCTION TYPE CODE:

FAS 1517
 BRIDGE
 SN 074-0086
 STA. 288+40.38
 TO
 STA. 290+04.38
 FED 80%
 STATE 20%
 X171-2A

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	592.0	592.0	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	26.0	26.0	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	676.0	676.0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	830.0	830.0	
40600300	AGGREGATE (PRIME COAT)	TON	17.0	17.0	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	98.0	98.0	
40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	7,118.0	7,118.0	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	80.0	80.0	
40800030	AGGREGATE (PRIME COAT)	TON	2.0	2.0	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	89.0	89.0	
44000100	PAVEMENT REMOVAL	SQ YD	7,100.0	7,100.0	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,156.0	1,156.0	
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	193.0	193.0	
44000700	APPROACH SLAB REMOVAL	SQ YD	86.0	86.0	
44004250	PAVED SHOULDER REMOVAL	SQ YD	345.0	345.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	60.0	60.0	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	912.0	912.0	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	694.0	694.0	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0		1.0
50104000	BRIDGE RAIL REMOVAL	FOOT	438.0		438.0

* SPECIALTY ITEM

(CONTINUED NEXT SHEET)

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\ppl_work\PW1001\SHERERJM\dms86674\050388-shr-500.dgn		DRAWN - JMS	REVISED -		1517	12VBR-1	PIATT	168	7				
	PLOT SCALE = 100.0000' / 1"	CHECKED - JMS	REVISED -		SCALE: N/A			SHEET NO. 2 OF 5 SHEETS		STA.	TO STA.	CONTRACT NO. 70388	
	PLOT DATE = 10/13/2009	DATE - 050609	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								