

NUMBER	ITEM	UNIT	TOTAL	FAP 326 (IL 47) RURAL TWO-LANE 80% FED/20% STATE X081-2A	FAP 326 (IL 47) RURAL TWO-LANE 100% LOCAL X081-2A
				QTY	QTY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	54	54	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	34	34	
20200100	EARTH EXCAVATION	CU YD	50	50	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	200	200	
20400800	FURNISHED EXCAVATION	CU YD	1155	575	580
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	249	249	
20800150	TRENCH BACKFILL	CU YD	11	11	
* 25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5	
* 25000314	SEEDING, CLASS 4B	ACRE	0.5	0.5	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	30	30	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	30	30	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	30	30	
25100630	EROSION CONTROL BLANKET	SQ YD	4018	4018	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	83	83	
28000315	AGGREGATE DITCH CHECKS	TON	80	80	
28000400	PERIMETER EROSION BARRIER	FOOT	1410	1410	
28000500	INLET AND PIPE PROTECTION	EACH	3	3	
28100109	STONE RIPRAP, CLASS A5	SQ YD	1629	1629	
28200200	FILTER FABRIC	SQ YD	1629	1629	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1085	1085	
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	66	66	
35501400	HOT-MIX ASPHALT BASE COURSE, VARIABLE DEPTH	TON	890	890	
35800100	PREPARATION OF BASE	SQ YD	1930	1930	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	255	255	
40600300	AGGREGATE (PRIME COAT)	TON	7	7	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	32	32	
40600990	TEMPORARY RAMP	SQ YD	536	536	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	165	165	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	100	100	
40800030	AGGREGATE (PRIME COAT)	TON	2	2	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	187	187	

NUMBER	ITEM	UNIT	TOTAL	FAP 326 (IL 47) RURAL TWO-LANE 80% FED/20% STATE X081-2A	FAP 326 (IL 47) RURAL TWO-LANE 100% LOCAL X081-2A
				QTY	QTY
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1654	827	827
44000100	PAVEMENT REMOVAL	SQ YD	66	66	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	680	680	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	442	442	
44000700	APPROACH SLAB REMOVAL	SQ YD	214	214	
44004250	PAVED SHOULDER REMOVAL	SQ YD	736	736	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	21	21	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	751	751	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	88	88	
50200100	STRUCTURE EXCAVATION	CU YD	502	502	
50300225	CONCRETE STRUCTURES	CU YD	320.2	320.2	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	835.8	835.8	
50300260	BRIDGE DECK GROOVING	SQ YD	1663	1663	
50300280	CONCRETE ENCASEMENT	CU YD	30.5	30.5	
50300300	PROTECTIVE COAT	SQ YD	2350	2350	
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	2252	2252	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	205960	205960	
50800515	BAR SPLICERS	EACH	1687	1687	
50900105	ALUMINUM RAILING, TYPE L	FOOT	402	402	
50901750	PARAPET RAILING	FOOT	396	396	
51201800	FURNISHING STEEL PILES HP14X73	FOOT	3526	3526	
51202305	DRIVING PILES	FOOT	3526	3526	
51203800	TEST PILE STEEL HP14X73	EACH	5	5	
51500100	NAME PLATES	EACH	1	1	
54213447	END SECTIONS 12"	EACH	2	2	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	89	89	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	123	123	
60100945	PIPE DRAINS 12"	FOOT	140	140	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	159	159	

FILE NAME : c:\pwork\p\001\STUL\STUL\0128986\0576428-dt-summary rev.dgn

*SPECIALTY ITEM



USER NAME = stults,jr	DESIGNED -	REVISED -
PLOT SCALE = 40.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 10/23/2009	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE: AS SHOWN	SHEET NO. 1 OF 2 SHEETS
STA.	TO STA.

F.A.P. RTE. 326	SECTION (137BR)BR	COUNTY CHAMPAIGN	TOTAL SHEETS 75	SHEET NO. 3
CONTRACT NO. 70428				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				