

EARTHWORK SCHEDULE

SEEDING SCHEDULE

STATION	(20201200) REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU.YD)	(20400800) FURNISHED EXCAVATION (CU.YD)
1301+75	N/A	N/A
1302+25	N/A	N/A
1302+75	N/A	N/A
1303+25	8.1	5.3
1303+75	17.9	10.2
1304+25	14.1	6.9
1304+66	5.3	0.6
1304+75	60.2	2.3
1305+25	32.8	2.3
1305+75	17.6	0.4
1306+25	9.3	7.3
1306+75	9.7	7.9
1307+25	8.3	0.9
1307+75	2.5	
1308+25		
TOTALS =	186.0	45.0

STATION	STATION	AREA (ACRE)	(28000250) TEMPORARY EROSION CONTROL SEEDING (POUND)	(25000210) SEEDING CLASS 2A (ACRE)	(25000350) SEEDING CLASS 7 (ACRE)	(25000400) NITROGEN FERTILIZER NUTRIENT (POUNDS)	(25000500) PHOSPHOR. FERTILIZER NUTRIENT (POUNDS)	(25000600) POTASS. FERTILIZER NUTRIENT (POUNDS)	(25100115) MULCH METHOD 2 (ACRE)
1301+75.00 LT	1308+25.00 LT	0.25	24.6	0.25	0.25	22.1	22.1	22.1	0.25
1301+75.00 RT	1308+25.00 RT	0.14	14.1	0.14	0.14	12.7	12.7	12.7	0.14
TOTAL =		0.4	39.0	0.4	0.4	35.0	35.0	35.0	0.4

DITCH CLEANING (Z0010555)

STATION	STATION	LT (FEET)	RT (FEET)
1302+25.00	1302+75.00	50.0	50.0
1302+75.00	1303+25.00	50.0	50.0
1304+25.00	1304+66.00		41.0
1305+75.00	1306+25.00		50.0
1306+25.00	1306+75.00		50.0
SUBTOTALS =		100.0	241.0
TOTAL =		341.0	

INLETS, TYPE A (60238800)

STATION	OFFSET	EACH
1304+67.00	35.80' LT	1.0
TOTAL =		1.0

GRATES, TYPE B (60402210)

STATION	OFFSET	EACH
1304+67.00	35.80' LT	1.0
TOTAL =		1.0