

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAP ROUTE 836 (IL 49)
 CHAMPAIGN COUNTY
 SN 010-8131
 STA. 1129+75.00 to STA. 1139+25
 RURAL TWO-LANE
 80% FED
 20% STATE
 CONSTRUCTION TYPE CODE: Y007

CODE NO	ITEM	UNIT	TOTAL QUANTITY
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
50200100	STRUCTURE EXCAVATION	CU YD	75.0
54021203	PRECAST CONCRETE BOX CULVERT 12' X 3' (M273)	FOOT	37.5
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	300.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1070.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1125.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	715.0
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1125.0
X4420099	CLASS D PATCHES, TYPE IV, 9 1/2 INCH	SQ YD	90.0
Z0010555	DITCH CLEANING	FOOT	100.0

• SPECIALTY ITEMS