

S.B.I. RTE. #	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SB14	(L-15D) B	MACOUPIN	21	6
STA. 1605+99.63 TO STA. 1625+33.72				
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				

EARTHWORK				
LOCATION				EARTH EXCAVATION
				CY
LT & RT	1614+00.00	TO	1818+48.00	75
LT & RT	1818+48.00		1818+92.00	80
LT & RT	1818+92.00		1819+00.00	115
TOTAL				270

SEEDING										
LOCATION		SEEDING CLASS 2	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	MULCH METHOD 2	AGRICULTURAL GROUND LIMESTONE		
		ACRES	POUND	POUND	POUND	POUND	ACRE	TON		
LT	1614+00.00	1818+81.33	0.1	10	9.0	9.0	9.0	0.1	0.2	
RT	1614+00.00	1819+00.00	0.1	10	9.0	9.0	9.0	0.1	0.2	
TOTAL			0.2	20	18.0	18.0	18.0	0.2	0.4	

PAVING SUMMARY								
LOCATION			PAVEMENT REMOVAL	AGGREGATE SHOULDERS, TYPE B 8"	PORTLAND CEMENT CONCRETE PAVEMENT 8"	GRANULAR CULVERT BACKFILL	PAVEMENT FABRIC	
			SY	SY	SY	CY	SY	
LT&RT	1614+50.00	1815+00.00	0	56	0	0	0	
LT&RT	1815+00.00	1815+32.00	0	50	0	0	0	
LT&RT	1815+32.00	1815+82.00	0	78	0	0	0	
LT&RT	1815+82.00	1816+48.00	0	103	0	0	0	
LT&RT	1816+48.00	1816+92.00	40	34	113	54	113	
LT&RT	1816+92.00	1817+57.00	0	101	0	0	0	
LT&RT	1817+57.00	1818+07.00	0	78	0	0	0	
LT&RT	1818+07.00	1818+31.33	0	38	0	0	0	
LT&RT	1818+31.33	1818+81.33	0	56	0	0	0	
TOTAL			40	592	113	54	113	

PIPE CULVERT		
LOCATION	PIPE CULVERTS, CORRUGATED STEEL, 15"	PIPE CULVERT REMOVAL
		FEET
RT	1815+00.00	60
LT	1815+50.00	60
RT	1815+79.61	15
LT	1815+93.27	20
RT	1817+52.20	15
RT	1818+00.00	60
TOTAL		180

GUARDRAIL IMPROVEMENT SCHEDULE							
LOCATION		SPBGR TYPE A	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL	TRAFFIC BARRIER TERMINAL TYPE 6	GUARDRAIL MARKERS TYPE A	TERMINAL MARKERS DIRECT APPLIED	
		FEET	EACH	EACH	EACH	EACH	
RT	1815+32.00	1816+59.00	50	1	1	1	1
LT	1815+82.00	1816+59.00	0	1	1	1	1
RT	1816+81.00	1817+57.00	0	1	1	1	1
LT	1816+81.00	1818+07.00	50	1	1	1	1
TOTAL			100	4	4	4	4

FENCING			
LOCATION			WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED
			FOOT
LT	1815+58.00	TO	1817+17.00
TOTAL			180

ENGINEER'S FIELD OFFICE TYPE B	
LOCATION	CAL MO
JOBSITE	6
TOTAL	6

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

PAVEMENT MARKINGS			
LOCATION			PAINT PAVEMENT MARKING SOLID YELLOW 5"
STATION	TO	STATION	FOOT
1815+32.00		1818+07.00	550
TOTAL			550

SILICONE JOINT SPECIAL	
LOCATION	FOOT
1816+59.00	16
1816+81.00	16
TOTAL	32

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NO SCALE  
DATE:

DRAWN BY PRL  
CHECKED BY JDR

Rev. 12-21-09