

S.B.L. RITE 4	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SB14	(L-150) B	MACOUPIN	21	4
STA. 1605+99.63		TO STA. 1625+33.72		
FED. ROAD DIST. NO. 6		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	X028-2A	
44000100	PAVEMENT REMOVAL	SQ YD	40	40	
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	592	592	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	50	50	
50800105	REINFORCEMENT BARS	POUND	10460	10460	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7410	7410	
50800305	WELDED WIRE FABRIC 6X6	SQ YD	113	113	
51500100	NAME PLATES	EACH	1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	100.7	100.7	
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	180	180	⚠
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	100	100	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NO SCALE
DATE:

DRAWN BY PRL
CHECKED BY JDR

⚠ Rev. 12-

* Specialty Items

S.B.I. RTE. #	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SB14	(L-15D) B	MACOUPIN	21	6
STA. 1605+89.63		TO STA. 1625+33.72		
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				

EARTHWORK				
LOCATION				EARTH EXCAVATION
				CY
LT & RT	1614+00.00	TO	1818+48.00	75
LT & RT	1818+48.00		1818+92.00	80
LT & RT	1818+92.00		1819+00.00	115
TOTAL				270

SEEDING									
LOCATION		SEEDING CLASS 2	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	AGRICULTURAL GROUND LIMESTONE	
		ACRES	POUND	POUND	POUND	POUND	ACRE	TON	
LT	1614+00.00	1818+81.33	0.1	10	9.0	9.0	9.0	0.1	0.2
RT	1614+00.00	1819+00.00	0.1	10	9.0	9.0	9.0	0.1	0.2
TOTAL			0.2	20	18.0	18.0	18.0	0.2	0.4

PAVING SUMMARY							
LOCATION		PAVEMENT REMOVAL	AGGREGATE SHOULDERS, TYPE B 8"	PORTLAND CEMENT CONCRETE PAVEMENT 8"	GRANULAR CULVERT BACKFILL	PAVEMENT FABRIC	
		SY	SY	SY	CY	SY	
LT&RT	1614+50.00	1815+00.00	0	58	0	0	
LT&RT	1815+00.00	1815+32.00	0	50	0	0	
LT&RT	1815+32.00	1815+82.00	0	78	0	0	
LT&RT	1815+82.00	1816+48.00	0	103	0	0	
LT&RT	1816+48.00	1816+82.00	40	34	113	54	
LT&RT	1816+82.00	1817+57.00	0	101	0	0	
LT&RT	1817+57.00	1818+07.00	0	78	0	0	
LT&RT	1818+07.00	1818+31.33	0	38	0	0	
LT&RT	1818+31.33	1818+81.33	0	56	0	0	
TOTAL			40	592	113	54	

PIPE CULVERT		
LOCATION	PIPE CULVERTS, CORRUGATED STEEL, 15"	PIPE CULVERT REMOVAL
		FOOT
RT	1815+00.00	60
LT	1815+50.00	60
RT	1815+79.61	15
LT	1815+93.27	20
RT	1817+52.20	15
RT	1818+00.00	40
TOTAL		180

GUARDRAIL IMPROVEMENT SCHEDULE						
LOCATION	SPBGR TYPE A	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL	TRAFFIC BARRIER TERMINAL TYPE 6	GUARDRAIL MARKERS TYPE A	TERMINAL MARKERS DIRECT APPLIED	
		FEET	EACH	EACH	EACH	EACH
RT	1815+32.00	1816+59.00	50	1	1	1
LT	1815+82.00	1816+59.00	0	1	1	1
RT	1816+81.00	1817+57.00	0	1	1	1
LT	1816+81.00	1818+07.00	50	1	1	1
TOTAL			100	4	4	4

FENCING			
LOCATION			WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED
			FOOT
LT	1815+58.00	TO	1817+17.00
TOTAL			180

ENGINEER'S FIELD OFFICE TYPE B	
LOCATION	CAL MO
JOBSITE	6
TOTAL	6

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

PAVEMENT MARKINGS		
LOCATION		PAINT PAVEMENT MARKING SOLID YELLOW 5"
STATION	TO	STATION
1815+32.00		1818+07.00
TOTAL		550

SILICONE JOINT SPECIAL	
LOCATION	FOOT
1816+59.00	16
1816+81.00	16
TOTAL	32

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NO SCALE
DATE:

DRAWN BY PRL
CHECKED BY JDR

Rev. 12-21-09