

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SB14	(L-150)B	MACOUPIN	21	2
STA.		TO STA.		
FED. ROAD DIST. NO. 6		ILLINOIS	FED. AID PROJECT	

INDEX OF SHEETS

SHT. NO.	DESCRIPTION
1	Cover Sheet
2	General Notes and Commitments
3-5	Summary of Quantities
6	Schedule of Quantities
7-9	Typical Sections
10	Alignments, Ties and Benchmarks
11	Traffic Control Plan
12	Plan and Profile
13-15	Structural Sheets
16	Soil Boring Logs
17	Details
18	Entrance Details
19-21	Cross Sections

GENERAL NOTES

- 1 Before ordering pipe culverts, the Contractor shall contact the Engineer as to the exact length and quantity required.
- 2 Where section or subsection monuments are encountered, The Engineer shall be notified before such monuments are removed. The Contractor shall protect and carefully preserve all monuments until an authorized Surveyor or agent has witnessed or otherwise referenced their location. The Contractor shall be responsible for having an authorized Surveyor reestablish any section or subsection monuments destroyed by his operations.
- 3 All areas disturbed by the Contractor during the construction of the project shall be seeded in accordance with Section 250 and mulched in accordance with Section 251 Mulch Method 2 of the Standard Specifications.

Item
Seeding, Class 2 (Special)
Nitrogen Fertilizer Nutrient - 90 lbs/ Acre
Phosphorus Fertilizer Nutrient - 90 lbs/ Acre
Potassium Fertilizer Nutrient - 90 lbs/ Acre
Agricultural Ground Limestone - 2 Ton/ Acre
Mulch, Method 2 - 2 Ton/ Acre
- 4 All elevations referring to U.S.G.S mean sea level datum.
- 5 Abandoned underground utilities that conflict with construction shall be disposed of outside the limits of the right of way according to Article 202.03 of the Standard Specifications and as directed by the Engineer. The work shall not be paid for separately but shall not be included in the cost of Earth Excavation.
- 6 Any Reference to a standard in these plans shall be interpreted to mean the edition as indicated by the sub number listed on the index of sheets or the copy of the standard included in these plans.
- 7 J.U.L.I.E. shall be notified a minimum of 48 hours in advance of any excavation - (800) 892-0123.
- 8 In addition to field surveys and aerial surveys, plan dimensions and details relative to the existing facilities have been taken from existing plans and are subject to construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field. Such variations shall not be a cause for additional compensation due to a change in the scope of the work. However, the Contractor will be paid for the quantity actually furnished at the bid price for the work.
- 9 All entrances shall remain accessible during and after construction.

STANDARDS

- 280001-05
- 420601-05
- 420701-02
- 420001-07
- 515001-03
- 630001-08
- 630301-05
- 631031-08
- 635001-01
- 635006-03
- 635011-02
- 701006-03
- 701901-01
- 780001-02
- 000001-05
- 001001-02
- BLR21-8

COMMITMENTS

- All entrances shall remain accessible during and after construction.
- The Field/Resident shall contact Studies and Plans concerning any major plan changes to make sure no previous commitments (not listed) were made affecting the design, and allow an improved design for future projects.
- 404 Permitting will need to be completed.

DISTRICT SIX	
EXAMINED <u>Feb 26</u> 20 <u>09</u>	<i>Joni A. Hoarns</i>
OPERATIONS ENGINEER	
EXAMINED <u>Feb 25</u> 20 <u>09</u>	<i>Joni A. Hoarns</i>
PROGRAM IMPLEMENTATION ENGINEER	
EXAMINED <u>October 14</u> 20 <u>09</u>	<i>ARMIL</i>
PROGRAM DEVELOPMENT ENGINEER	

All dimensions are in inches unless otherwise shown.

REVISIONS	
DATE	NAME

ILLINOIS DEPARTMENT OF TRANSPORTATION
GENERAL NOTES AND COMMITMENTS
 SCALE: NO SCALE
 DATE
 DRAWN BY PRL
 CHECKED BY LDB