

S.B.I. RTE. 4	SECTION (L-15D) B	COUNTY MACOUPIN	TOTAL SHEETS 21	SHEET NO. 3
STA. 1605+99.63 TO STA. 1625+33.72				
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				

LOCATION OF WORK				80% FED 20% STATE (BOX CULVERT)	
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	X028-2A	
20200100	EARTH EXCAVATION	CU YD	270	270	
25000200	SEEDING, CLASS 2	ACRE	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18.0	18.0	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18.0	18.0	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18.0	18.0	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.4	0.4	
25100115	MULCH, METHOD 2	ACRE	0.2	0.2	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
28100107	STONE RIPRAP, CLASS A4	SQ YD	100	100	
28200200	FILTER FABRIC	SQ YD	152	152	
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	113	113	
42001200	PAVEMENT FABRIC	SQ YD	113	113	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NO SCALE
DATE:

DRAWN BY PRL
CHECKED BY JDR

Rev.