

S.B.I. RTE. 4	SECTION (L-15D) B	COUNTY MACOUPIN	TOTAL SHEETS 21	SHEET NO. 4
STA. 1605+99.63		TO STA. 1625+33.72		
FED. ROAD DIST. NO. 6		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				80% FED 20% STATE (BOX CULVERT)	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	X028-2A	
44000100	PAVEMENT REMOVAL	SQ YD	40	40	
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	592	592	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	50	50	
50800105	REINFORCEMENT BARS	POUND	10460	10460	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7410	7410	
50800305	WELDED WIRE FABRIC 6X6	SQ YD	113	113	
51500100	NAME PLATES	EACH	1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	100.7	100.7	
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	442	442	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	100	100	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	

* Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NO SCALE
DATE:

DRAWN BY PRL
CHECKED BY JDR