



STA. 808+76.30 (43° SKEW FWD LT)
 EX STRUCTURE TBR AND
 EX PAVEMENT AND APPROACHES TBR
 PR 10' X 10' RC BOX CULVERT (SEE DETAILS)
 PR GRANULAR BACKFILL
 PR HMA BASE COURSE 10"

TEMPORARY SOIL RETENTION SYSTEM
 (SEE STRUCTURE PLANS)

TEMPORARY PAVEMENT
 MARKING - LINE 4"
 (SOLID WHITE)

STA. 807+50 TO STA. 809+20
 REMOVE & REPLACE BOX CULVERT & PAVEMENT,
 HMA BASE COURSE 10".
 CONSTRUCT FINAL EARTHWORK, SEED & RIPRAP.
 (SEE CULVERT DETAILS)

LEGEND

- WORK AREA
- SIGN
- TYPE III BARRICADE
- DRUM WITH STEADY BURNING LIGHT
- TRAFFIC SIGNAL
- TYPE C BIDIRECTIONAL REFLECTOR
- TEMPORARY CONCRETE BARRIER
- IMPACT ATTENUATOR
- STEADY BURNING LIGHTS AND DOUBLE VERTICAL PANELS
- TRAFFIC FLOW

NOTES:
 THE CONTRACTOR SHALL STAKE OUT THE CONSTRUCTION LIMITS PRIOR TO ANY TREE REMOVAL. THE ENGINEER WILL THEN IDENTIFY ANY TREES TO BE SAVED. NO TREES SHALL BE REMOVED UNTIL THE ENGINEER HAS IDENTIFIED ALL TREES TO BE SAVED.

NOTE:
 SEE "STORM WATER POLLUTION PREVENTION PLANS" FOR TEMPORARY EROSION CONTROL.

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC STAGE 2			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pw\work\PWIDOT\LAUGHLINRL\0169540\811\STAGING2.dgn		DRAWN - TRF	REVISED -		SCALE: 1"=20'	SHEET NO.	OF SHEETS	STA. 806+00 TO STA. 812+00	325	114 (B-1)	MACOUPIN	57	20
PLOT SCALE = 48.0000' / IN.		CHECKED - RG	REVISED -						CONTRACT NO. 72646				
PLOT DATE = Oct-21-2009 11:08:53AM		DATE - 7/31/09	REVISED -						ILLINOIS FED. AID PROJECT				