SUMMARY OF QUANTITIES

				STP			ROADWAY RESURFACING
				RDWY. WIDENING F.A.P. 662 80% FEDERAL 20% STATE	ROADWAY F.A.P. 662 80% FEDERAL 20% STATE	STRUCTURE S.N. 059-7004 80% FEDERAL 20% STATE	PARKING LANES 50% STATE 50% VILLAGE
				CONSTRUCTION TYPE CODE			CONSTRUCTION TYPE CODE
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	1000-2A	1000-2A	X028-2A	Y025
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2		2		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	797		797		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	312	59	253		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	399			399	
X0324118	GRANULAR CULVERT BACKFILL	CU YD	234			234	
X0325129	TREE REMOVAL	L SUM	1		1		
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1		1		
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	36019		36019		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	.5	.5		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2		2		
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2		2		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1		
* Z0054517	ROCK FILL - FOUNDATION	TON	354			354	

*Specialty Items

FILE NAME = S:\PROJ ENGR I (Negangard)\Dust Squad\FAP 662 (IL 4)Henderson pdfs\CADD Sheets\06727DRAWNS00.dgn	USER NAME = madonsovj	DESIGNED -	REVISED -
			REVISED -
	PLOT SCALE = 2.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Aug-17-2009 04:12:57PM	DATE -	REVISED -

Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL. Design Firm
No. 184-001907

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. 4 OF 4 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	D(W-3,RS-11,CR)	MACOUPIN	102	6
		CONTRACT NO. 72765		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT