

**SCHEDULE
GUARDRAIL**

LOCATION	TBT TY 1	GUARDRAIL	TEMP	TEMP	TERMINAL	BIDIRECTIONAL
	SPCL TAN	REMOVAL	SPBGR, TY A	SPBGR, ATTCH TO STRUCT	MARKER DIRECT APPLIED	GUARDRAIL REFLECTORS
	EACH	FOOT	FOOT	FOOT	EACH	EACH
STA. 449+14.5 TO STA. 449+64.5 LT.	1	50			1	
STA. 449+64.5 TO STA. 449+77 LT.		12.5	12.5			
STA. 449+77 TO STA. 449+89.5 LT.		12.5		12.5		
STA. 449+89.5 TO STA. 450+02 LT.		12.5	12.5			
STA. 450+02 TO STA. 450+52 LT.	1	50			1	
STA. 449+64.5 LT.						1
STA. 450+02 LT.						1
TOTAL	2	137.5	25	12.5	2	2

**SCHEDULE
SURFACE REMOVAL BUTT JOINT**

LOCATION	HMA	PCC
	SQ. YD.	SQ. YD.
STA. 354+28 TO STA. 354+68 C	171.7	
GEORGE ST. LT. & RT.	42.1	
STA. 394+20.10 TO STA. 394+50.10 C	73.3	
STA. 394+60.56 TO STA. 394+90.56 C	73.3	
STA. 513+03.14 TO STA. 513+38.14 C	117.5	
CENTER ST. LT & RT.	99.4	
MADISON ST. LT. & RT.	97.7	
STA. 33+94 TO STA. 34+04 C	44.4	
FROM ENTRANCE SCHEDULES	1523	55
TOTAL	2243	55

**SCHEDULE
RAISED REFLECTIVE PAVEMENT MARKER**

LOCATION	RRPM	RRPM
	EACH	REMOVAL
STA. 352+50 TO STA. 373+85	108	59
STA. 373+85 TO STA. 421+37.11	60	59
STA. 421+40.62 TO STA. 513+03.14	115	115
STA. 513+03.14 TO STA. 518+63.85	15	14
STA. 7+90.71 TO STA. 34+04	66	65
TOTAL	364	312

**SCHEDULE
FURNISHING & ERECTING ROW MARKERS**

LOCATION	QUANTITY
	EACH
STA. 448+25.77, 60' RT.	1
STA. 448+25.52, 65' RT.	1
STA. 449+50, 80' RT.	1
STA. 450+00, 130' RT.	1
STA. 450+75, 130' RT.	1
STA. 451+50, 60' RT.	1
STA. 448+20.50, 60' RT.	1
STA. 448+75, 100' RT.	1
STA. 449+50, 100' RT.	1
STA. 451+00, 60' RT.	1
TOTAL	10

**SCHEDULE
RIPRAP & FILTER FABRIC**

LOCATION	STONE DUMPED	FILTER FABRIC
	RIPRAP, CLASS A4	SQ. YD.
STA. 365+41.7 TO STA. 366+00 RT.	73	147
STA. 448+00 TO STA. 450+50 LT.	420	839
STA. 449+00 TO STA. 451+00 RT.	420	839
TOTAL	913	1825

**SCHEDULE
CONTROLLED LOW-STRENGTH MATERIAL**

LOCATION	QUANTITY
	CU. YD.
STA. 354+39.5 LT TO STA. 354+41.8 RT	16.8
STA. 365+72.3 C	33.2
TOTAL	50

**SCHEDULE
SURFACE REMOVAL**

LOCATION	HMA SURF REM	HMA SURF REM	HMA SURF REM
	1/2'	2/4'	VAR DEPTH
	SQ. YD.	SQ. YD.	SQ. YD.
STA. 352+50 TO STA. 354+28	791		
STA. 354+28 TO STA. 373+85			4686
STA. 373+85 TO STA. 394+20.10			4975
STA. 394+90.56 TO STA. 421+37.11			6469
STA. 421+40.62 TO STA. 446+25			6073
STA. 454+75 TO STA. 513+03.14			14247
STA. 513+38.14 TO STA. 518+63.85		1285	
STA. 7+90.70 TO STA. 33+94		6364	
PARKING LANES			
STA. 513+38.14 TO STA. 518+63.85 LT & RT		935	
STA. 7+90.71 TO STA. 11+80 LT & RT		692	
STA. 11+80 TO STA. 33+94 LT & RT		4428	
TOTAL	791	13704	36450

FILE NAME =
S:\PROJ\ENGR 1 (Nogengard)\Dust Squad\F

USER NAME = mcdonnavj
P 662 IL 4) Henderson.pdf\CADD Sheets\067

DESIGNED -
DRAWN - schedule.dgn

CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -



Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL
62703 Phone: (217)544-8033 IL Design Firm
No. 184-001907

SCHEDULE OF QUANTITIES
SCALE: NONE SHEET NO. 3 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	DW-3,RS-11,CR	MACOUPIN	102	9

CONTRACT NO. 72765
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT