

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	90% FED. 10% STATE TOTAL QUANTITY	ROADWAY F.A.P. 717 1000-2A	STRUCTURE S.N. 054-0514 X081-2A	
20200100	EARTH EXCAVATION	CU YD	4746.4	4746.4		
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	40	40		
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	404.6	404.6		
* 20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	173.0		173.0	
25000200	SEEDING, CLASS 2	ACRE	0.85	0.85		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	77	77		
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	77	77		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	77	77		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.7	1.7		
25100115	MULCH, METHOD 2	ACRE	0.85	0.85		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	600.0	600.0		

* SEE SPECIAL PROVISIONS

USER NAME:	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SHEET 1 OF 7	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	DRAWN -	REVISED -			717	I09B-3	LOGAN	73	3	
PLOT SCALE:	CHECKED -	REVISED -			CONTRACT NO. 72A88					
PLOT DATE:	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT