

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY F.A.P. 717 1000-2A	STRUCTURE S.N. 054-0514 X081-2A	
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	999.0		999.0	
* 50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	106,630		106,630	
50800515	BAR SPLICERS	EACH	897		897	
* 51200958	FURNISHING METAL SHELL PILES 14" x 0.250"	FOOT	1,052.0		1,052.0	
* 51202305	DRIVING PILES	FOOT	1,052.0		1,052.0	
51203200	TEST PILE METAL SHELLS	EACH	4		4	
* 51205200	TEMPORARY SHEET PILING	SQ FT	1,984.0		1,984.0	
51500100	NAME PLATES	EACH	1		1	
* 54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	62.0	62.0		
* 54215547	METAL END SECTIONS 12"	EACH	4	4		
* 54215553	METAL END SECTIONS 18"	EACH	2	2		
* 59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	93.4		93.4	
* 60105000	PIPE DRAINS, CORRUGATED STEEL OR ALUMINUM ALLOY 12"	FOOT	40	40		

* SEE SPECIAL PROVISIONS

Rev.

USER NAME:	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SHEET 4 OF 7			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN -	REVISED -		717	109B-3	LOGAN	73	6			
PLOT SCALE:	CHECKED -	REVISED -		CONTRACT NO. 72A88							
PLOT DATE:	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		