

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY F.A.P. 717 1000-2A	STRUCTURE S.N. 054-0514 X081-2A	
* 60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	128.0		128.0	
60900215	TYPE C INLET BOX, STANDARD 609001	EACH	4	4		
# * 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	750	750		
# * 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
# * 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
* 63200310	GUARDRAIL REMOVAL	FOOT	395.0	395.0		
* 66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	9		
* 67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
67100100	MOBILIZATION	L SUM	1	1		
* 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
* 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
* 70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		

* SEE SPECIAL PROVISIONS

SPECIALTY ITEMS

USER NAME:	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SHEET 5 OF 7	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	DRAWN -	REVISED -			717	109B-3	LOGAN	73	7	
PLOT SCALE:	CHECKED -	REVISED -			CONTRACT NO. 72A88					
PLOT DATE:	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT