

SCHEDULE OF QUANTITIES

GUARDRAIL REMOVAL 63200310			
LOCATION	STATION	TO STATION	FOOT
RT	305+29	306+52	123
LT	305+80	306+52	72
RT	307+78	308+78	100
LT	307+78	308+78	100
TOTAL			395

REMOVAL OF EXISTING PRECAST CONCRETE UNITS X0324744			
LOCATION	STATION	TO STATION	SQ FT
LT	306+52	306+72	75
RT	306+52	306+72	75
LT	307+58	307+78	75
RT	307+58	307+78	75
TOTAL			300

BUTT / JOINT RAMP SCHEDULE					
STATION	TO STATION	PAVEMENT WIDTH	DISTANCE	40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	40600990 TEMPORARY RAMP (SQ YD)
		(FEET)		(SQ YD)	(SQ YD)
301+87	301+92	24	5		14
301+87	302+17	24	30	80	
305+69	305+74	24	5		14
308+04	308+09	24	5		14
311+69	312+14	24	30	80	
312+09	312+14	24	5		14
TOTALS				160	56

PAVEMENT REMOVAL 44000100					
LOCATION	STATION	TO STATION	LENGTH FOOT	WIDTH FOOT	SO YD
	305+74	306+72	98	24	261.3
	307+58	308+04	46	24	122.7
RT	302+36	306+52	416	4	184.9
RT	307+78	310+64	286	4	127.1
RT	303+12	306+52	340	4	151.1
RT	307+78	311+44	366	4	162.7
TOTAL					1009.8

TEMPORARY CONCRETE BARRIER 70400100			
STAGE	STATION	TO STATION	FOOT
I	303+27.5	310+65	737.5
TOTAL			737.5

GUARDRAIL MARKERS, TYPE A 78200410			
LOCATION	STATION	TO STATION	EACH
LT	303+48	305+92	4
RT	302+70	305+87	4
LT	307+92	311+10	4
RT	307+85	310+28	4
TOTAL			16

TRAFFIC BARRIER TERMINAL, TYPE 6 63100085				
LOCATION	STATION	TO STATION	STAGE	EACH
LT	305+48	305+92	II	1
RT	305+43	305+87	I	1
LT	307+92	308+35	II	1
RT	307+85	308+29	I	1
TOTAL				4

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS 66600105		
LOCATION	STATION	EACH
RT 40'	303+35	1
RT 69.92'	305+33.21	1
RT 80'	306+00	1
RT 80'	307+95	1
RT 70'	307+95	1
RT 70'	308+78.75	1
LT 66.5'	310+32.00	1
LT 40'	310+87.00	1
RT 40'	311+15	1
TOTAL		9

RELOCATE TEMPORARY CONCRETE BARRIER 70400200			
STAGE	STATION	TO STATION	FOOT
II	303+27.5	310+65	737.5
TOTAL			737.5

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT 63100167			
LOCATION	STATION	TO STATION	EACH
LT	303+48.49	303+98.49	1
RT	302+70.21	303+20.21	1
LT	310+60.32	311+10.32	1
RT	309+78.98	310+28.98	1
TOTAL			4

TERMINAL MARKERS, DIRECT APPLIED 78201000		
LOCATION	STATION	EACH
LT	303+48	1
RT	302+70	1
LT	311+10	1
RT	310+29	1
TOTAL		4

TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL) TANGENT X7050167			
LOCATION	STATION	TO STATION	EACH
LT	304+98	305+48	1
LT	309+22.82	309+72.82	1
TOTAL			2

BARRIER WALL MARKERS, TYPE B 78200520			
LOCATION	STATION	TO STATION	EACH
LT	305+92	307+92	3
RT	305+87	307+85	3
TOTAL			6

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS 63000001			
LOCATION	STATION	TO STATION	FOOT
LT	303+98.49	305+48.49	150
RT	303+20.21	305+45.21	225
LT	308+35.32	310+60.32	225
RT	308+28.98	309+78.98	150
TOTAL			750

STRIPING SCHEDULE									
STATION	TO STATION	LT/RT	70300100 SHORT TERM PAVEMENT MARKING (FOOT)	70301000 WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	780001120 PAINT PAVEMENT MARKING - LINE 5"		78100100 RAISED REFLECTIVE PAVEMENT MARKER (EACH)	78300100 PAVEMENT MARKING REMOVAL (SQ FT)	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
					WHITE (FOOT)	YELLOW (FOOT)			
301+87	312+14	-	309	35			13		13
301+87	312+14	-			1027	257		822	
301+87	312+14	-			1027			1239	
SUB-TOTALS					2054	257			
TOTALS			309	35	2311	13	2061	13	

USER NAME:	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES 1 OF 2			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE:	DRAWN -	REVISED -					717	I09B-3	LOGAN	73	10
PLOT DATE:	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 72A88				
	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							