

SUB-BASE GRANULAR MATERIAL, TYPE A 8"			
LOCATION			SQ YDS
US 24 - SAFETY			
LT STA 13+92.40	TO	LT STA 23+50.00	479.49
LT STA 23+50.00	TO	LT STA 31+77.57	744.56
RT STA 13+96.27	TO	RT STA 22+19.49	531.12
RT STA 25+35.05	TO	RT STA 31+77.57	563.55
US 24 SAFETY TOTAL			2318.72
IL 99 SOUTH - SAFETY			
RT STA 0+11.71	TO	RT STA 1+75.00	186.26
SAFETY TOTAL			2504.98
US 24 - NHS			
LT STA 31+77.57	TO	LT STA 34+19.55	282.52
LT STA 34+19.55	TO	LT STA 43+00.00	1051.70
LT STA 43+00.00	TO	LT STA 50+89.28	887.13
RT STA 31+77.57	TO	RT STA 34+19.55	217.88
LT STA 34+19.55	TO	RT STA 43+00.00	877.65
RT STA 43+00.00	TO	RT STA 51+25.65	952.86
US 24 NHS TOTAL			4269.74
NHS TOTAL			4269.74

GRAND TOTAL	6,775
-------------	-------

SUB-BASE GRANULAR MATERIAL, TYPE A 4"			
LOCATION			SQ YDS
JEFFERSON ST			
STA 9+25.85	TO	STA 9+74.52	210.50
STA 10+13.04	TO	STA 10+48.22	171.43
JEFFERSON ST TOTAL			381.93
NORTH STREET			
STA 10+07.00	TO	STA 11+66.57	482.63
SAFETY TOTAL			864.56
COUNTRY LANE			
STA 10+18.00	TO	STA 10+50.71	125.70
NHS TOTAL			125.70

GRAND TOTAL	990
-------------	-----

HOT-MIX ASPHALT BASE COURSE WIDENING, 11"			
LOCATION			SQ YDS
US 24			
LT STA 14+22.40	TO	LT STA 23+50.00	166.27
LT STA 23+50.00	TO	LT STA 31+77.57	420.67
RT STA 13+96.27	TO	RT STA 22+19.49	312.23
RT STA 25+35.05	TO	RT STA 31+77.57	317.53
SAFETY LIMITS TOTAL			1216.70
US 24			
LT STA 31+77.57	TO	LT STA 34+50.00	212.22
LT STA 34+50.00	TO	LT STA 43+00.00	689.02
LT STA 43+00.00	TO	LT STA 50+89.28	532.36
RT STA 31+77.57	TO	RT STA 34+50.00	138.88
RT STA 34+50.00	TO	RT STA 43+00.00	520.94
RT STA 43+00.00	TO	RT STA 51+25.65	563.00
NHS LIMITS TOTAL			2656.42
GRAND TOTAL			3873

SUB-BASE GRANULAR MATERIAL, TYPE C			
LOCATION			TON
US 24 / IL 99 SOUTH INTERSECTION			
SW QUADRANT ISLAND - SAFETY			
RT STA 22+91.50	TO	RT STA 23+29.94	26.4
SE QUADRANT ISLAND - SAFETY			
RT STA 23+62.23	TO	RT STA 23+87.79	20.5
SAFETY TOTAL			46.9
US 24 - NHS			
LT STA 49+20.00	TO	LT STA 50+89.00	22.6
RT STA 49+20.00	TO	RT STA 51+25.00	28.7
NHS TOTAL			51.3

GRAND TOTAL	98
-------------	----

HOT-MIX ASPHALT BASE COURSE, 6"			
LOCATION			SQ YDS
JEFFERSON ST			
STA 9+25.85	TO	STA 9+74.52	169.60
STA 10+13.04	TO	STA 10+48.22	130.72
JEFFERSON ST TOTAL			300.32
NORTH STREET			
STA 10+44.78	TO	STA 11+66.57	400.02
SAFETY LIMITS TOTAL			700.34
COUNTRY LANE			
STA 10+18.02	TO	STA 10+50.71	96.38
NHS LIMITS TOTAL			96.38
GRAND TOTAL			797

CONSTRUCTING TEST STRIP - NHS		
LOCATION		L SUM
JOBSITE		2
TOTAL		2

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30				
LOCATION			AREA (SQ YD)	(TONS)
JEFFERSON ST - SAFETY				
STA 9+25.85	TO	STA 9+74.52	169.60	19.00
STA 10+13.04	TO	STA 10+48.22	130.72	14.64
NORTH STREET - SAFETY				
STA 10+44.78	TO	STA 11+66.57	400.02	44.80
SAFETY TOTAL				78.44
COUNTRY LANE - NHS				
STA 10+18.02	TO	STA 10+50.71	96.38	10.79
GRAND TOTAL				90

NOTE: SEE LOCATION MAP ON COVER SHEET FOR FUNDING LIMITS ie. SAFETY, STP, AND NHS.

LEVELING BINDER (MACHINE METHOD), N70							
LOCATION			LENGTH (FOOT)	PAVEMENT WIDTH (FOOT)	AREA (SQ YD)	QUANTITY (TONS)	
US 24 - SAFETY							
STA 14+26.33	TO	STA 19+44.75	518.42	26	1,497.66	83.87	
STA 19+44.75	TO	STA 20+84.03	139.28	26.00	37.04	487.79	27.32
STA 20+84.03	TO	STA 22+19.49	135.46	37.04	39.52	576.16	32.26
STA 22+19.49	TO	STA 24+32.25	212.76	39.52	36.48	898.32	50.31
STA 24+32.25	TO	STA 25+34.95	102.70	36.48	36.00	413.54	23.16
STA 25+34.95	TO	STA 31+77.57	642.62	36	2,570.48	143.95	
US 24 SAFETY TOTAL							360.87
IL 99 SOUTH SAFETY							
STA 0+28.96	TO	STA 1+75.26	146.30	CADD	1175.49	65.83	
SAFETY TOTAL							426.70
US 24 - NHS							
STA 31+77.57	TO	STA 34+50.00	272.43	36	1,089.72	61.02	
STA 34+50.00	TO	STA 43+00.00	850.00	36	3,400.00	190.40	
STA 43+00.00	TO	STA 48+64.83	564.83	36	2,259.32	126.52	
STA 48+64.83	TO	STA 49+20.38	55.55	36.00	35.61	221.00	12.38
STA 49+20.38	TO	STA 50+89.21	168.83	35.61	24.78	566.42	31.72
STA 50+89.21	TO	STA 51+25.58	36.37	24.81	25.68	102.02	5.71
STA 51+25.58	TO	STA 52+00.00	74.42	24.84	205.40	11.50	
NHS TOTAL							439.25
IL 99 SOUTH - STP							
STA 1+75.26	TO	STA 4+65.62	290.36	37.9	28.00	1,063.04	59.53
STA 4+65.62	TO	STA 5+28.00	62.38	30	207.93	11.64	
IL 99 SOUTH STP TOTAL							71.17
GRAND TOTAL							937

TEMPORARY RAMP						
LOCATION			LENGTH (FOOT)	PAVEMENT WIDTH (FOOT)	AREA (SQ YD)	
US 24 - NHS						
STA 636+07.83	TO	STA 636+14.50	6.67	25.00	18.53	
DAMON RD - LT			6.67	33.60	24.90	
BUCKHORN RD - RT			6.67	37.40	27.72	
SOUTH ST - RT			6.67	66.20	49.06	
MAIN ST - LT			6.67	22.70	16.82	
OAK ST - LT			6.67	26.20	19.42	
WEST CROSS ST - RT			6.67	45.20	33.50	
CAPITAL ST - LT			6.67	58.70	43.50	
CAPITAL ST - RT			6.67	59.80	44.32	
SE CROSS ST - LT			6.67	24.50	18.16	
SE CROSS ST - RT			6.67	37.50	27.79	
COUNTRY LN - LT			6.67	18.46	13.68	
STA 51+70.00	TO	STA 52+00.00	5.00	25.00	13.89	
NHS TOTAL						351.29
JEFFERSON ST - LT			6.67	22.43	16.62	
JEFFERSON ST - RT			6.67	25.37	18.80	
NORTH ST - LT			6.67	23.16	17.16	
SAFETY TOTAL						52.58
IL 99 SOUTH - STP						
STA 5+21.33	TO	STA 5+28.00	6.67	37.50	27.79	
IL 99 NORTH - STP						
STA 51+76.64	TO	STA 51+83.31	6.67	24.00	17.79	
NORTH ST - LT			6.67	46.00	34.09	
NORTH ST - RT			6.67	49.00	36.31	
WASHINGTON ST - RT			6.67	46.00	34.09	
WEST CROSS ST - RT			6.67	38.80	28.76	
WASHINGTON ST - LT			6.67	36.90	27.35	
HIGHLAND PARK DR - LT			6.67	28.00	20.75	
GRANDVIEW ST - RT			6.67	21.60	16.01	
LYNN ROSE HEIGHTS DR - LT			6.67	27.80	20.60	
STP TOTAL						263.54
GRAND TOTAL						667