

TEMPORARY PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS		
LOCATION	DIRECTION	QUANTITY (SQ FT)
WHITE TURN ARROWS		
US 24 - NHS		
STA 667+59	LEFT	15.6
STA 667+97	LEFT	15.6
STA 668+58	LEFT	15.6
STA 0+28	LEFT	15.6
STA 0+69	LEFT	15.6
STA 0+37	RIGHT	15.6
STA 1+07	RIGHT	15.6
STA 5+79	RIGHT	15.6
STA 6+15	RIGHT	15.6
STA 7+29	RIGHT	15.6
STA 7+67	RIGHT	15.6
STA 32+06	LEFT	15.6
STA 32+26	LEFT	15.6
STA 33+83	LEFT	15.6
STA 34+03	LEFT	15.6
STA 35+07	LEFT	15.6
STA 35+27	LEFT	15.6
STA 36+78	LEFT	15.6
STA 36+98	LEFT	15.6
STA 38+25	LEFT	15.6
STA 38+45	LEFT	15.6
STA 40+12	LEFT	15.6
STA 40+32	LEFT	15.6
STA 42+06	LEFT	15.6
STA 42+26	LEFT	15.6
STA 44+06	LEFT	15.6
STA 44+26	LEFT	15.6
STA 46+06	LEFT	15.6
STA 46+26	LEFT	15.6
STA 48+21	LEFT	15.6
STA 48+41	LEFT	15.6
NHS TOTAL		483.6
US 24 - SAFETY		
STA 21+18	RIGHT	15.6
STA 21+93	RIGHT	15.6
STA 24+07	LEFT	15.6
STA 24+84	LEFT	15.6
STA 26+05	LEFT	15.6
STA 26+25	LEFT	15.6
STA 28+29	LEFT	15.6
STA 28+49	LEFT	15.6
STA 30+27	LEFT	15.6
STA 30+47	LEFT	15.6
US 24 SAFETY TOTAL		156
IL 99 SOUTH SAFETY		
STA 0+17	RIGHT	15.6
STA 0+85	LEFT	15.6
STA 1+49	LEFT	15.6
STA 0+89	RIGHT	15.6
STA 1+49	RIGHT	15.6
IL 99 SOUTH SAFETY TOTAL		78
SAFETY TOTAL		234
IL 99 NORTH - STP		
STA 11+26	LEFT	15.6
IL 99 NORTH STP TOTAL		15.6
IL 99 SOUTH STP		
STA 2+09	LEFT	15.6
STA 2+09	RIGHT	15.6
IL 99 SOUTH STP TOTAL		31.2
STP TOTAL		46.8
GRAND TOTAL		764

LOCATION	LENGTH FOOT	* OF APPLICATIONS	SHORT-TERM PAVEMENT MARKING LENGTH FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT
US 24 - NHS				
STA 636+07.83 TO STA 651+53.44	1545.61	2	309.20	64.4
STA 651+53.44 TO STA 660+88.80	935.36	2	187.00	39.0
STA 660+88.80 TO STA 661+74.30 BK	85.50	2	17.20	3.6
STA 661+74.30 BK = 659+40.87 AH				
STA 659+40.87 A TO STA 668+96.40	955.53	2	191.20	39.8
STA 668+96.40 BK = STA 0+00.00 AH				
STA 0+00.00 TO STA 6+70.92	670.92	2	134.20	28.0
STA 6+70.92 TO STA 13+78.40	707.48	2	141.40	29.5
STA 34+55.28 TO STA 48+64.81	1409.53	3	423.00	58.8
STA 48+64.81 TO STA 52+00.00	335.19	3	100.50	14.0
NHS TOTALS			1503.70	276.92
US 24 - SAFETY				
STA 13+78.40 TO STA 23+45.95	967.55	3	290.40	40.3
STA 23+45.95 TO STA 31+20.00	774.05	3	232.20	32.3
STA 31+20.00 TO STA 34+55.28	335.28	3	100.50	14.0
IL 99 - SOUTH				
STA 0+11.71 TO STA 5+28.00	516.29	2	103.20	21.5
SAFETY TOTALS			726.30	108.04
IL 99 NORTH - STP				
STA 10+51.00 TO STA 16+58.11	607.11	2	121.40	25.3
STA 16+58.11 TO STA 26+23.00	964.89	2	193.00	40.2
STA 26+23.00 TO STA 36+15.79	992.79	2	198.60	41.4
STA 36+15.79 TO STA 59+90.86	2375.07	2	475.00	99.0
STA 59+90.86 BK = STA 50+00.00 AH				
STA 50+00.00 TO STA 51+83.31	183.31	2	36.60	7.6
IL 99 NORTH STP TOTALS			1024.60	213.46
GRAND TOTALS			3,255	598

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"		LENGTH (FOOT)
LOCATION		
WHITE STOP BARS		
US 24 - NHS		
STA 668+15		24.00
STA 668+28		38.00
STA 668+57		26.00
STA 0+07		24.00
STA 0+09		18.00
STA 6+28		30.00
STA 6+42		29.00
STA 6+71		31.00
STA 7+14		30.00
STA 13+67		11.00
COUNTRY LN		9.30
NHS TOTAL		270.30
US 24 - SAFETY		
STA 13+78		18.30
STA 23+00		12.00
STA 23+82		24.00
JEFFERSON ST		12.50
JEFFERSON ST		11.20
NORTH ST		32.20
IL 99 - SOUTH		
STA 0+28		15.00
STA 0+53		12.00
STA 0+61		15.00
SAFETY TOTAL		152.20
IL 99 NORTH -STP		
STA 16+43		15.00
STA 17+25		22.30
STA 17+26		12.50
STA 25+42		18.00
STP TOTAL		67.80
GRAND TOTAL		490

TEMPORARY PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"					
LOCATION			LENGTH (FOOT)	* OF LINES	LENGTH (FOOT)
WHITE TURN LANES					
US 24 - NHS					
STA 659+84	TO	STA 660+89	27	1	27
STA 667+59	TO	STA 668+15	56	1	56
STA 668+15	TO	STA 668+22	66	1	66
STA 668+21	TO	STA 668+28	72	1	72
STA 668+53	TO	STA 668+56	68	1	68
STA 668+21	TO	STA 0+03	66	4	264
STA 668+93	TO	STA 0+06	75	1	75
STA 0+02	TO	STA 0+09	73	1	73
STA 0+11	TO	STA 0+68	58	1	58
STA 1+05	TO	STA 2+54	38	1	38
STA 2+95	TO	STA 3+03	61	2	122
STA 5+04	TO	STA 5+78	18	1	18
STA 5+77	TO	STA 6+28	51	1	51
STA 6+33	TO	STA 6+38	60	1	60
STA 6+39	TO	STA 6+41	65	1	65
STA 6+40	TO	STA 7+04	61	4	244
STA 7+03	TO	STA 7+04	65	1	65
STA 7+09	TO	STA 7+10	60	1	60
STA 7+15	TO	STA 7+67	51	1	51
STA 7+67	TO	STA 8+35	17	1	17
NHS TOTAL					1550
US 24 - SAFETY					
STA 19+40	TO	STA 21+14	44	1	44
STA 20+72	TO	STA 20+96	23	2	46
STA 21+13	TO	STA 22+45	132	1	132
STA 23+03	TO	STA 23+13	34	2	68
STA 23+82	TO	STA 24+84	102	1	102
STA 24+84	TO	STA 25+84	25	1	25
US 24 SAFETY TOTAL					417
IL 99 SOUTH - SAFETY					
STA 0+31	TO	STA 0+48	17	2	34
STA 0+34	TO	STA 0+50	42	2	84
STA 0+47	TO	STA 0+68	24	2	48
STA 0+81	TO	STA 1+75	94	1	94
IL 99 SOUTH SAFETY TOTAL					260
SAFETY TOTAL					677
IL 99 NORTH - STP					
STA 11+26	TO	STA 11+32	7	1	7
STA 11+32	TO	STA 11+99	17	1	17
IL 99 NORTH STP TOTAL					24
IL 99 SOUTH - STP					
STA 1+75	TO	STA 2+09	34	1	34
STP TOTAL					58
GRAND TOTAL					2,285

	TRAFFIC CONTROL AND PROTECTION,			
	SAFETY L SUM	NHS L SUM	STP L SUM	TOTAL L SUM
STANDARD 701201	0.2	0.4	0.4	1
STANDARD 701306	0.2	0.4	0.4	1
STANDARD 701326	0.2	0.4	0.4	1
STANDARD 701501	0.2	0.4	0.4	1
STANDARD 701701	0.2	0.4	0.4	1
STANDARD 701801	0.2	0.4	0.4	1

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
SAFETY	6
NHS	6
STP	6
TOTAL	18

MOBILIZATION				
LOCATION	SAFETY L SUM	NHS L SUM	STP L SUM	TOTAL L SUM
JOBSITE	0.2	0.4	0.4	1