

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS
- 2 LIST OF ILLINOIS DOT HIGHWAY STANDARDS
- 3 GENERAL NOTES
- 4-12, 12A, 12B SUMMARY OF QUANTITIES
- 13-31 TYPICAL CROSS SECTIONS
- 32-34A, 35-39 SCHEDULE OF QUANTITIES
- 50-54 ALIGNMENT & BENCH MARKS
- 55 CROSS TIES
- 56-58 STAGE CONSTRUCTION DETAILS
- 59-74 PLAN SHEETS - IL 4
- 75 PLAN SHEETS - LAWRENCE AVE
- 76-78 PLAN SHEETS - OLD JACKSONVILLE RD/MONROE ST
- 79-84 PLAN SHEETS - MONROE ST
- 85-89 PROFILES
- 90-93 REMOVAL PLANS - IL 4
- 94-99 REMOVAL PLANS - OLD JACKSONVILLE RD/MONROE ST
- 100-104 DRAINAGE - IL 4
- 105 DRAINAGE - LAWRENCE AVE
- 106-109 DRAINAGE - OLD JACKSONVILLE RD/MONROE ST
- 110-114 ELEVATIONS - IL 4
- 115-118 ELEVATIONS - OLD JACKSONVILLE RD/MONROE ST
- 119-134 PAVEMENT MARKING DETAILS - IL 4
- 135 PAVEMENT MARKING DETAILS - LAWRENCE AVE
- 136-144 PAVEMENT MARKING DETAILS - OLD JACKSONVILLE RD/MONROE ST
- 145-148 CROSSWALK & ISLAND DETAILS
- 150 CONCRETE GUTTER & PAVED DITCH DETAILS
- 151 CONCRETE MEDIAN TYPE SM-6 (DOWELED) DETAIL
- 152 CONCRETE COLLAR DETAILS
- 152 RETAINING WALL DETAILS
- 153 ENTRANCE DETAILS
- 154 INLET ADJUSTMENT DETAILS
- 155 BUTT JOINT DETAILS
- 155 LONGITUDINAL JOINT REPAIR
- 155 PREFORMED JOINT SEAL TREATMENT
- 156-159 STORM WATER POLLUTION PREVENTION PLAN
- 160-164 EROSION CONTROL PLAN - IL 4
- 165-169 EROSION CONTROL PLAN - OLD JACKSONVILLE RD/MONROE ST
- 170 PRISMATIC CURB REFLECTOR
- 170A-170L LIGHTING PLAN
- 170M-170R TEMPORARY LIGHTING PLAN
- 170S CIRCUIT DIAGRAM
- 170T-170Z LIGHTING DETAILS
- 171-188 TRAFFIC SIGNAL DETAILS
- 188A-188B BORING LOGS
- 189-216 CROSS SECTIONS - IL 4
- 217-230 CROSS SECTIONS - OLD JACKSONVILLE RD/MONROE ST
- 231-236 CROSS SECTIONS - MONROE ST
- 237-240 CROSS SECTIONS - RICKARD RD
- 241-244 CROSS SECTIONS - OLD JACKSONVILLE RD - SOUTH LEG

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
- 280001-05 TEMPORARY EROSION CONTROL SYSTEMS
- 420001-07 PAVEMENT JOINTS
- 420701-02 PAVEMENT FABRIC
- 424001-05 CURB RAMPS FOR SIDEWALKS
- 442001-04 CLASS A PATCHES
- 442101-07 CLASS B PATCHES
- 542301-02 PRECAST REINFORCED CONCRETE FLARED END SECTION
- 601001-03 SUBSURFACE DRAINS
- 601101-01 CONCRETE HEADWALL FOR PIPE DRAIN
- 602301-02 INLET TYPE A
- 602306-02 INLET TYPE B
- 602401-02 MANHOLE TYPE A
- 602601-02 PRECAST REINFORCED CONCRETE FLAT SLAB TOP
- 602701-02 CAST IRON STEPS
- 604001-03 FRAME AND LIDS TYPE 1
- 604006-04 FRAME AND GRATE TYPE 3
- 604041-02 FRAME AND GRATE TYPE 9
- 604091-02 FRAME AND GRATE TYPE 24
- 606001-04 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 606101-04 TYPE A GUTTER INLET, OUTLET AND ENTRANCE
- 606201-02 TYPE B GUTTER
- 606301-04 PC CONCRETE ISLANDS AND MEDIANS
- 606401-01 PAVED DITCH
- 701101-02 OFF ROAD OPERATIONS 2L, 2W, MORE THAN 15 AWAY
- 701106-02 OFF ROAD OPERATIONS 2L, 2W 15 TO 24 FROM PAVEMENT EDGE
- 701326-03 LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH
- 701421-02 LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS 45 MPH TO 55 MPH
- 701422-02 LANE CLOSURE, MULTILANE, FOR SPEEDS 45 MPH TO 55 MPH
- 701426-03 LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS ≥ TO 45 MPH
- 701501-05 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701701-06 URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701801-04 LANE CLOSURE, MULTILANE 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE
- 701901-01 TRAFFIC CONTROL DEVICES
- 720016-02 MAST ARM MOUNTED STREET NAME SIGNS
- 780001-02 TYPICAL PAVEMENT MARKINGS
- 781001-03 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS
- 814001-02 HANDHOLES
- 814006-02 DOUBLE HANDHOLES
- 857001-01 STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
- 862001-01 UNINTERRUPTABLE POWER SUPPLY (UPS)
- 873001-02 TRAFFIC SIGNAL GROUNDING & BONDING
- 876001-01 PEDESTRIAN PUSH BUTTON POST
- 877001-04 STEEL MAST ARM ASSEMBLY AND POLE 16' THROUGH 55'
- 878001-08 CONCRETE FOUNDATION DETAILS
- 880001-01 SPAN WIRE MOUNTED SIGNALS AND FLASHING BEACON INSTALLATION
- 880006-01 TRAFFIC SIGNAL MOUNTING DETAILS
- BLR 21-8 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS
- BLR 22-6 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS (TWO-LANE TWO WAY RURAL TRAFFIC) (ROAD CLOSED TO THRU TRAFFIC)

COMMITMENTS:

1. THE RESIDENT ENGINEER SHALL CONTACT STUDIES AND PLANS CONCERNING ANY MAJOR PLAN CHANGE TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN AND ALLOW AN IMPROVED DESIGN FOR FUTURE PROJECTS.
2. THERE IS AN NPDES STORM WATER POLLUTION PREVENTION PLAN WITH THIS PROJECT.
3. THERE IS AN AGREEMENT WITH THE CITY OF SPRINGFIELD.
4. THE DEPARTMENT HAS GIVEN A WRITTEN COMMITMENT TO RICKARD ROAD DEVELOPMENT THAT THE CURRENT RICKARD ROAD DESIGN WILL NOT CHANGE TO PRESERVE THE DESIGN SIGHT DISTANCE.
5. THE PROPERTY OWNERS FOR RICKARD ROAD DEVELOPMENT (STA. 43+15) AND POWERPLAY PROPERTIES (STA. 46+99, 74) WILL NEED TO HAVE THAT PART OF THEIR SPRINKLER SYSTEM THAT IS LOCATED IN THE TE AREA REMOVED AND CAPPED OFF BY A PROFESSIONAL SPRINKLER COMPANY BEFORE CONSTRUCTION BEGINS. THE PROPERTY OWNERS WILL HAVE UNTIL APRIL 1, 2010 TO HAVE THIS WORK COMPLETED.

DISTRICT SIX

EXAMINED Oct 19 2009

[Signature]
OPERATIONS ENGINEER

EXAMINED October 2 2009

[Signature]
PROGRAM DEVELOPMENT ENGINEER

EXAMINED Oct 8 2009

[Signature]
PROGRAM IMPLEMENTATION ENGINEER

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS/STANDARDS

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	2
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 72899	