

LOCATION OF WORK	NHF 80% FEDERAL 20% STATE	100% ESP	NHF 80% FEDERAL 10% STATE 10% CITY*	100% ESP	NHF 80% FEDERAL 10% STATE 10% CITY	50% STATE 50% CITY
	ROADWAY VETERANS PARKWAY WASHINGTON ST LAWRENCE AVE	ROADWAY OLD JACKSONVILLE RD, MONROE ST	TRAFFIC SIGNALS @ IL 4 & MONROE ST/OLD JACKSONVILLE RD	TRAFFIC SIGNALS CLOCKTOWER DR	TRAFFIC SIGNALS WASHINGTON & LAWRENCE	SIDEWALK AT WASHINGTON ST AND LAWRENCE AVE
	STA 274+00 TO STA 365+50	*ARRA ELIGIBLE TO MAX OF \$2.174M FED FUNDS, THEN CITY (MFT) FUNDS				

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
-----------------------	--	--	-------	------------------------	--	--	--	--	--

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	I000	Y031-1F	Y031-1F	Y031-1F	SFTY-1B
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	105	105					
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	420	420					
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	1,309	1,074	235				
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	58	41	17				
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	119	62	57				
44213000	PATCHING REINFORCEMENT	SQ YD	1,827	1,827					
44213200	SAWCUTS	FOOT	19,129	17,873	1,256				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,520	1,358	162				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	789	745	44				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,612	1,612					
48203105	HOT-MIX ASPHALT SHOULDERS, SPECIAL	TON	3,763	3,598	165				
50300225	CONCRETE STRUCTURES	CU YD	15.9		15.9				
50800105	REINFORCEMENT BARS	POUND	790		790				
54200451	PIPE CULVERTS, TYPE 1 RCCP 36"	FOOT	14	14					
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1					
54248515	CONCRETE COLLAR	EACH	4	1	3				
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	1,572	1,298	274				
55100500	STORM SEWER REMOVAL 12"	FOOT	759	387	372				
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	323	245	78				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2	2					
60107600	PIPE UNDERDRAINS 4"	FOOT	2,685	2,685					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	38	38					
60224600	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3		3				

CEC Cummins Engineering Corporation <small>Civil and Structural Engineering</small>	JOB # 2200.4	DESIGNED - NAK	REVISED -
	FILE NAME = D672899-shr-500.dgn	DRAWN - AJH	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED - NAK	REVISED -
	PLOT DATE = Oct-29-2009 09:07:15AM	DATE - 10/15/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	6
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72B99	