

LOCATION OF WORK	NHE 80% FEDERAL 20% STATE	100% ESP	NHE 80% FEDERAL 10% STATE 10% CITY*	100% ESP	NHE 80% FEDERAL 10% STATE 10% CITY	50% STATE 50% CITY	
	ROADWAY VETERANS PARKWAY WASHINGTON ST LAWRENCE AVE	ROADWAY OLD JACKSONVILLE RD, MONROE ST	TRAFFIC SIGNALS @ IL 4 & MONROE ST/OLD JACKSONVILLE RD	TRAFFIC SIGNALS CLOCKTOWER DR	TRAFFIC SIGNALS WASHINGTON & LAWRENCE	SIDEWALK AT WASHINGTON ST AND LAWRENCE AVE	
	STA 274+00 TO STA 365+50	*ARRA ELIGIBLE TO MAX OF \$2.174M FED FUNDS, THEN CITY (MFT) FUNDS					

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
-----------------------	--	--	-------	------------------------	--	--	--	--	--

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000	1000	Y031-1F	Y031-1F	Y031-1F	SFTY-1B
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	519	366	153				
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	413	208	205				
60610900	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	223	161	62				
60615500	PAVED DITCH, TYPE A-15 (SPECIAL)	FOOT	913	913					
60617515	PAVED DITCH, TYPE B-30 (SPECIAL)	FOOT	790	790					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	8,306	7,549	757				
60622354	CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)	SQ FT	5,760		5,760				
66410300	CHAIN LINK FENCE REMOVAL	FOOT	792		792				
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	144		144				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12					
67100100	MOBILIZATION	L SUM	1	1					
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1					
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1					
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		1				
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1		1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	80	40	40				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	44	44					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18,771	13,114	5,657				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3,494	1,643	1,851				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	14,362	7,148	7,214				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	21,633	9,246	12,387				



JOB = 2200.4	DESIGNED - NAK	REVISED -
FILE NAME = D672B99-shr-S00.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 40.0000' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = Oct-29-2009 09:07:35AM	DATE - 10/15/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	8
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				