

LOCATION OF WORK	NHF 80% FEDERAL 20% STATE	100% ESP	NHF 80% FEDERAL 10% STATE 10% CITY*	100% ESP	NHF 80% FEDERAL 10% STATE 10% CITY	50% STATE 50% CITY	NHF 80% FED. 20% STATE
	ROADWAY VETERANS PARKWAY WASHINGTON ST LAWRENCE AVE	ROADWAY OLD JACKSONVILLE RD, MONROE ST	TRAFFIC SIGNALS @ IL 4 & MONROE ST/OLD JACKSONVILLE RD	TRAFFIC SIGNALS CLOCKTOWER DR	TRAFFIC SIGNALS WASHINGTON & LAWRENCE	SIDEWALK AT WASHINGTON ST AND LAWRENCE AVE	LIGHTING
	STA 274+00 TO STA 365+50	*ARRA ELIGIBLE TO MAX OF \$2.174M FED FUNDS, THEN CITY (MFT) FUNDS					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
URBAN				1000	1000	Y031-1F	Y031-1F	Y031-1F	SFTY-1B	Y030-1E
CODE NO.	ITEM	UNIT	TOTAL QUANTITY							
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2,535	1,048	1,487					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	616	182	434					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	9,641	5,182	4,459					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,086	1,457	629					
72000200	SIGN PANEL - TYPE 2	SQ FT	65						65	
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	7,910	996	6,914					
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,063	1,019	1,044					
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	2,583	1,248	1,335					
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	7,930	5,900	2,030					
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	9,272	5,075	4,197					
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	1,093	557	536					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,162	830	332					
78200300	PRISMATIC CURB REFLECTOR	EACH	502	316	186					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,196	378	3,818					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	537	537						
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	3							3
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1,720			909	811			
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	126			48	78			
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	114			103	11			
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	129			118	11			
* 81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	1,079							1,079
81021540	CONDUIT, AUGERED 1 1/2" DIA., PVC	FOOT	236			111	125			
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	260			67	193			
81021580	CONDUIT, AUGERED 3 1/2" DIA., PVC	FOOT	92			92				
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	604			510	94			
81306100	JUNCTION BOX (SPECIAL)	EACH	7			3	4			

*Specialty Items Rev.



JOB # 2200.4	DESIGNED - NAK	REVISED -
FILE NAME = D672899-shr-500.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 48.0000 ' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = Oct-29-2009 09:07:48AM	DATE - 10/15/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF	SHEETS
	STA.	TO	STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	9
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. (ILLINOIS) FED. AID PROJECT				