

LOCATION OF WORK				NHF 80% FEDERAL 20% STATE ROADWAY VETERANS PARKWAY WASHINGTON ST LAWRENCE AVE STA 274+00 TO STA 365+50	100% ESP ROADWAY OLD JACKSONVILLE RD, MONROE ST	NHF 80% FEDERAL 10% STATE 10% CITY* TRAFFIC SIGNALS @ IL 4 & MONROE ST/OLD JACKSONVILLE RD	100% ESP TRAFFIC SIGNALS CLOCKTOWER DR	NHF 80% FEDERAL 10% STATE 10% CITY TRAFFIC SIGNALS WASHINGTON & LAWRENCE	NHF 80% FED. 20% STATE LIGHTING
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000	1000	Y031-1F	Y031-1F	Y031-1F	Y030-1E
Z0033600	LONGITUDINAL JOINT REPAIR	FOOT	11,510	11,510					
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	2,641	2,641					
Z0075300	TIE BARS	EACH	182	182					
X6025900	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	1	1					
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	50			50			
X4060400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	FOOT	2,380	740	1,640				
81603000	UNIT DUCT, 600V, 2-1 C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	4,716						4,716
81603040	UNIT DUCT, 600V, 2-1 C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1,767						1,767
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	2,840						2,840
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 1400 WATT	EACH	32						32
82104000	LUMINAIRE, SODIUM VAPOR, MULTI- MOUNT, 400 WATT	EACH	19						19
82500510	LIGHTING CONTROLLER, TYPE CB- RCS 60AMP - 240 VOLT	EACH	2						2
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1						1
83004600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	32						32
83057340	LIGHT POLE, WOOD, 60 FOOT, CLASS 3	EACH	15						15
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" x 8"	EACH	32						32
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	128						128
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	15						15
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	25						25
84200700	LIGHTING FOUNDATION REMOVAL	EACH	25						25
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	3						3
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	3						3
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	3						3



JOB - 2200.4	DESIGNED - NAK	REVISED -
FILE NAME - 0672899-shr-S00.dgn	DRAWN - AJH	REVISED -
PLOT SCALE - 48.0000' / IN.	CHECKED - NAK	REVISED -
PLOT DATE - Oct-29-2009 09:08:31AM	DATE - 10/15/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.S. RTE. 662	SECTION (2-1-2, 2-2) RS, TS-6	COUNTY SANGAMON	TOTAL SHEETS 244	SHEET NO. 12A
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

Rev.

CONTRACT NO. 72B99