

LOCATION OF WORK	NHF 80% FEDERAL 20% STATE	100% ESP	NHF 80% FEDERAL 10% STATE 10% CITY*	100% ESP	NHF 80% FEDERAL 10% STATE 10% CITY	50% STATE 50% CITY
	ROADWAY VETERANS PARKWAY WASHINGTON ST LAWRENCE AVE	ROADWAY OLD JACKSONVILLE RD, MONROE ST	TRAFFIC SIGNALS @ IL 4 & MONROE ST/OLD JACKSONVILLE RD	TRAFFIC SIGNALS CLOCKTOWER DR	TRAFFIC SIGNALS WASHINGTON & LAWRENCE	SIDEWALK AT WASHINGTON ST AND LAWRENCE AVE
	STA 274+00 TO STA 365+50	*ARRA ELIGIBLE TO MAX OF \$2.174M FED FUNDS, THEN CITY (MFT) FUNDS				

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
-----------------------	--	--	-------	------------------------	--	--	--	--	--

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	I000	Y031-1F	Y031-1F	Y031-1F	SFTY-1B
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4			1	1	2	
* 89502380	REMOVE EXISTING HANDHOLE	EACH	16			13	3		
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	12			7	5		
* X0301183	GEOMETRICALLY PROGRAMMED LOUVER	EACH	12			12			
* X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	4			1	1	2	
X0322729	MATERIAL TRANSFER DEVICE	TON	5,314	5,314					
* X0322929	CAMERA MOUNTING ASSEMBLY	EACH	6			2	4		
* X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	2,308			885	491	932	
X0323381	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 12"	FOOT	362	177	185				
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1					
X0325991	ELECTRIC CABLE IN CONDUIT, COMMUNICATION, NO. 18, 3/C	FOOT	3,530			1,223	705	1,602	
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	246	129	117				
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	2,072	2,072					
X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	2,035	2,035					
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	44,097	37,473	6,624				
* X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	5,913	4,489	1,424				
* X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	1,930	1,314	616				
* X8170245	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 12	FOOT	1,223			1,223			
* X8950200	REBUILD EXISTING HANDHOLE	EACH	11					11	
XX003503	FLARED END SECTION REMOVAL	EACH	1	1					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0017100	DOWEL BARS	EACH	2,100	1,622	478				
Z0023700	FILLING EXISTING HANDHOLES	EACH	4	4					

\*Specialty Items



JOB = 2200.4	DESIGNED - NAK	REVISED -
FILE NAME = D672899-shht-S001.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 40.0000 ' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = Oct-29-2009 09:08:19AM	DATE - 10/15/2009	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	12
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				