

TEMPORARY PAVEMENT MARKING - LINE 6"

LOCATION	SOLID WHITE FOOT	WHITE 2' DASH 6' SKIP FOOT	TOTAL FOOT
STAGE 1			
WB OLD JACKSONVILLE RD			
STA 44+06.73 TO STA 45+89.73	183.00		183.00
STA 49+80.00 TO STA 50+75.00		24.00	24.00
WB W MONROE ST			
STA 50+69.00 TO STA 53+52.00	283.00		283.00
STA 51+14.45 TO STA 53+83.96	269.51		269.51
RICKARD RD			
STA 10+59.00 CROSSWALK	63.00		63.00
STA 10+65.00 CROSSWALK	54.00		54.00
STA 10+63.70 TO STA 11+71.00	107.30		107.30
STAGE 2			
EB OLD JACKSONVILLE RD			
STA 40+72.35 TO STA 42+11.05		36.00	36.00
STA 43+83.55 TO STA 48+33.20	449.65		449.65
STA 45+11.65 TO STA 48+76.00	364.35		364.35
STA 45+11.65 TO STA 49+74.60	462.95		462.95
STA 49+05.00 TO STA 50+76.00		50.00	50.00
STA 48+69.00 TO STA 50+45.00		52.00	52.00
EB W MONROE ST			
STA 9+10.70 TO STA 10+82.75	172.05		172.05
STA 9+10.70 TO STA 10+82.75	172.05		172.05
STA 10+89.55 CROSSWALK	87.00		87.00
STA 10+95.55 CROSSWALK	93.00		93.00
WB MONROE ST			
STA 50+76.05 TO STA 55+72.35	496.30		496.30
STA 6+56.47 TO STA 6+79.95	23.48		23.48
STAGE 3			
SB VETERANS PARKWAY			
STA 324+81.75 TO STA 332+07.20	725.45		725.45
STA 327+34.80 TO STA 332+41.45	506.65		506.65
NB VETERANS PARKWAY			
STA 333+81.25 TO STA 337+89.75	408.50		408.50
STA 334+11.50 TO STA 341+21.20	709.70		709.70
TOTAL	5,630.94	162.00	5,792.94

TEMPORARY PAVEMENT MARKING - LINE 8"

LOCATION	SOLID WHITE FOOT
STAGE 1	
WB OLD JACKSONVILLE RD	
STA 43+85.00 TO STA 44+06.75	61
LT STA 48+89.10 TO STA 49+44.50	213
LT STA 40+10.00 TO STA 41+60.00	307
WB MONROE ST	
LT STA 50+46.15 TO STA 51+14.45	194
STAGE 2	
EB OLD JACKSONVILLE RD	
STA 42+11.00 TO STA 43+55.00	144
STA 42+11.00 TO STA 43+60.00	149
STA 43+55.00 TO STA 43+60.00	12
RT STA 48+33.20 TO STA 49+02.80	197
EB MONROE ST	
RT STA 50+04.65 TO STA 50+58.45	210
STAGE 3	
SB VETERANS PARKWAY	
STA 324+17.00 TO STA 327+35.00	318
STA 324+17.00 TO STA 327+35.00	318
NB VETERANS PARKWAY	
STA 337+90.00 TO STA 340+99.00	169
STA 337+90.00 TO STA 340+99.00	243
TOTAL	2,535

TEMPORARY PAVEMENT MARKING - LINE 12"

LOCATION	SOLID WHITE FOOT
STAGE 1	
WB OLD JACKSONVILLE RD	
LT STA 48+89.10 TO STA 49+44.50	67.5
LT STA 40+10.00 TO STA 41+60.00	71.0
WB MONROE ST	
LT STA 50+46.15 TO STA 51+14.45	83.4
STAGE 2	
EB OLD JACKSONVILLE RD	
STA 42+11.00 TO STA 43+55.00	70.8
RT STA 48+33.20 TO STA 49+02.80	80.4
EB MONROE ST	
RT STA 50+04.65 TO STA 50+58.45	61.2
STAGE 3	
SB VETERANS PARKWAY	
STA 324+17.00 TO STA 327+35.00	95.4
NB VETERANS PARKWAY	
STA 337+90.00 TO STA 340+99.00	86.3
TOTAL	616.0

TEMPORARY PAVEMENT MARKING - LINE 5"

LOCATION	WHITE SKIP DASH FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	TOTAL FOOT
STAGE 1				
WB OLD JACKSONVILLE RD				
STA 40+50.00 TO STA 43+29.00	70			70
STA 43+84.00 TO STA 49+30.00	140			140
STA 40+50.00 TO STA 43+29.00			279	279
STA 43+84.00 TO STA 49+05.00			521	521
WB W MONROE ST				
STA 50+68.00 TO STA 55+72.35	130			130
STA 6+56.47 TO STA 10+89.00	110			110
RICKARD RD				
STA 10+65.70 TO STA 11+71.00			105	105
STA 10+65.70 TO STA 11+71.00			105	105
STAGE 2				
EB OLD JACKSONVILLE RD				
STA 40+50.00 TO STA 48+77.00	210			210
WB OLD JACKSONVILLE RD				
STA 43+84.00 TO STA 48+52.00			468	468
EB W MONROE ST				
STA 50+68.00 TO STA 55+72.35	130			130
STA 6+56.47 TO STA 10+89.00	110			110
STA 50+96.00 TO STA 55+72.35			875	875
STA 6+56.47 TO STA 10+89.54			875	875
WB W MONROE ST				
STA 50+96.00 TO STA 55+72.35			875	875
STA 6+56.47 TO STA 10+89.54			875	875
STAGE 3				
SB VETERANS PARKWAY				
STA 322+06.00 TO STA 332+18.00			1,012	1,012
STA 327+34.80 TO STA 332+53.90		519		519
STA 322+41.00 TO STA 332+07.00			966	966
STA 334+05.00 TO STA 339+16.00			511	511
NB VETERANS PARKWAY				
STA 326+06.00 TO STA 331+85.00			579	579
STA 333+46.00 TO STA 337+90.00			444	444
STA 334+04.00 TO STA 343+23.00			919	919
STA 334+11.50 TO STA 343+61.00		950		950
TOTAL	900	1,469	9,410	11,778

TEMPORARY PAVEMENT MARKING LINE 24"

LOCATION	DESCRIPTION	STOP BAR FOOT
STAGE 1		
MONROE ST		
STA 50+68.00	MAINLINE	25.0
STA 50+93.00	RT TURN	18.0
STA 50+76.00	LT TURN	12.0
RICKARD RD		
STA 10+68.00	MAINLINE/RT TURN	12.0
STA 10+70.00	MAINLINE/LT TURN	12.0
STAGE 2		
OLD JACKSONVILLE RD		
STA 48+39.00	MAINLINE	12.0
STA 48+52.00	LT TURN	12.0
STA 48+70.00	RT TURN	18.0
STA 48+77.00	MAINLINE	36.0
MONROE ST		
STA 50+97.00	LT TURN	12.0
STA 11+91.00	MAIN/RT/LT TURN	36.0
STA 10+83.00	RT TURN	17.4
STA 11+91.00	MAIN/RT/LT TURN	40.0
STAGE 3		
SB VETERANS PARKWAY		
STA 332+61.00	RT TURN	18.0
STA 332+23.00	LT TURN	17.4
STA 332+50.00	LT TURN	17.9
NB VETERANS PARKWAY		
STA 333+59.00	RT TURN	18.0
STA 333+72.00	LT TURN	18.0
STA 334+03.00	LT TURN	17.7
TOTAL		369.4

PAVEMENT MARKING REMOVAL

LOCATION	LINE WIDTH INCHES	QTY SQ FT
STAGE 1		
WB OLD JACKSONVILLE RD		
TO STA 49+00.00	5	354
TO STA 43+47.00	6	149
TO STA 43+29.00	5	124
TO STA 49+38.00	6	69
TO STA 49+38.00	6	25
WB W MONROE ST		
TO STA 53+49.00	6	148
TO STA 53+49.00	6	148
TO STA 55+72.35	5	216
TO STA 11+08.00	5	189
TO STA 51+06.00	6	96
TO STA 51+06.00	6	25
STOP BARS		
STA 50+53.00	24	50
STA 50+53.00	24	24
STA 50+76.00	24	36
ARROWS		
THROUGH		11.5
THRU & LT TURN		26.0
RT TURN		15.6
LT TURN		15.6
THROUGH		11.5
THROUGH		11.5
THRU & LT TURN		26.0
RT TURN		15.6
THRU & LT TURN		26.0
RT TURN		15.6
LT TURN		15.6
STAGE 2		
EB OLD JACKSONVILLE RD		
TO STA 43+47.00	6	138
TO STA 49+00.00	5	315
TO STA 49+00.00	6	142
TO STA 49+00.00	6	66
TO STA 49+08.00	8	125
TO STA 49+08.00	12	50
TO STA 50+76.00	6	25
TO STA 50+45.00	6	26
EB W MONROE ST		
TO STA 55+72.35	5	216
TO STA 11+08.00	5	189
TO STA 55+14.00	6	32
TO STA 11+08.00	6	71
TO STA 50+52.00	8	126
TO STA 50+52.00	12	50
STOP BARS		
STA 49+00.00	24	24
STA 49+00.00	24	50
STA 49+00.00	24	36
STA 11+08.00	24	24
STA 11+08.00	24	50
STA 11+08.00	24	36
ARROWS		
LT TURN		15.6
RT TURN		15.6
RT TURN		15.6
RT TURN		15.6
LT TURN		15.6
RT TURN		15.6
LT TURN		15.6
LT TURN		15.6
LT TURN		15.6
LT TURN		15.6
LT TURN		15.6
LT TURN		15.6
LT TURN		15.6
STAGE 3		
NB VETERANS PARKWAY		
TO STA 324+17.00	5	88
TO STA 324+81.00	5	100
SB VETERANS PARKWAY		
TO STA 343+54.00	5	97
TO STA 343+22.00	5	93
TOTAL		4,196



JOB = 2200.4	DESIGNED - NAK	REVISED -
FILE NAME = D672B99-shd-schedule.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 48.0000 ' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = Oct-29-2009 11:33:06AM	DATE - 6/26/2008	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.
--------	-----------	-----------	------	---------

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	49
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				