



STORM SEWERS

NO.	LOCATION	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" EACH	STORM SEWERS, TYPE 1, RCCP, CL 4, 12" FOOT	USFL ELEVATION	DSFL ELEVATION	CLSM
IL4 - WB TURN LANE						
S32	18.25' LT - 14' LT	STA 337+75	4.25	604.5	604.3	0.4
S33	12' LT - 12' RT	STA 337+75	24	604.2	604.0	4.8
S34	14' RT - 17.25' RT	STA 337+75	3.25	603.9	603.7	0.2
S35	20.25' RT - 70.25' RT	STA 337+75	50	603.6	603.2	4.5
S36	70.25' RT - 76.25' RT	STA 337+75	1	603.2	603.1	
S37	18.75' RT STA 337+76.5 TO 18.75' RT STA 338+99		122.5	603.9	603.7	15.7
S38	6.75' RT - 17.75' RT	STA 337+75	11	604.2	604.0	1.0
SHEET TOTAL			1	215		26.6

STRUCTURES

NO.	LOCATION	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	FLOWLINE GRATE	FLOWLINE 12" EAST	FLOWLINE 12" WEST	FLOWLINE 12" NORTH	FLOWLINE 12" SOUTH
IL4 - WB TURN LANE									
A33	18.75' LT STA 337+75	1			607.22		604.5		
B34	13.00' LT STA 337+75		1		607.05	604.3	604.2		
B35	13.00' RT STA 337+75		1		606.80	604.0	603.9		
M36	18.75' RT STA 337+75			1	607.22	603.7	603.6		603.6
A37	6.25' RT STA 339+00	1			606.16		604.2		
B39	18.75' RT STA 339+00		1		606.58	604.0		603.9	
SHEET TOTAL		2	3	1					



JOB = 2200.4
 FILE NAME = d672B99-shr-drain1.dgn
 PLOT SCALE = 48,0000 "/ IN.
 PLOT DATE = Oct-29-2009 11:48:29AM

DESIGNED - NAK
 DRAWN - AJH
 CHECKED - NAK
 DATE - 10/08/2009

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

IL 4 (VETERANS PARKWAY) - DRAINAGE

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	103
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				