

CODE NO.	ITEM	UNIT	90% FED. 10% STATE TOTAL QUANTITY 1000
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	269
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	24,233
60624600	CORRUGATED MEDIAN	SQ FT	904
64200105	SHOULDER RUMBLE STRIP	FOOT	105,773
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70103710	TRAFFIC CONTROL FOR RAMP	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20,845
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6,879
* 72400500	RELOCATE SIGN PANEL ASSEMBLY-TYPE A	EACH	3
* 72400600	RELOCATE SIGN PANEL ASSEMBLY-TYPE B	EACH	2
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LETTER AND SYMBOLS	SQ FT	577.2

CODE NO.	ITEM	UNIT	90% FED. 10% STATE TOTAL QUANTITY 1000
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 5"	FOOT	27,961
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 8"	FOOT	5,954
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 12"	FOOT	1,439
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 24"	FOOT	238
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3,294
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3,274
Δ X2503000	MAINTENANCE MOWING	ACRE	252
Δ X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	195
X0322729	MATERIAL TRANSFER DEVICE	TON	50,358
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	146,890
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	2,192
Z0017100	DOWEL BARS	EACH	160
Z0075300	TIE BARS	EACH	104

Δ Non-participating

* INDICATES SPECIALITY ITEM

FILE NAME =	USER NAME = *USER#	DESIGNED - R.A.W.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
#FILE#		DRAWN - R.A.W.	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	I-55	84-1-2RS4150RS1	SANGAMON	65	5
	PLOT SCALE = *SCALE#	CHECKED - J.S.A.	REVISED -												
	PLOT DATE = *DATE#	DATE - 7/24/09	REVISED -											CONTRACT NO. 72C38	

ILLINOIS FED. AID PROJECT